

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02091-00-00
Spot: SEWNNE , Sec/Twnshp/Rge: 13-10S-20W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: SUTOR Well Number: 4
County: ROOKS Total Vertical Depth: 3747 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3744
Surface Casing Size: 8.625 feet: 252

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/01/2003 9:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JOE STRUBE Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered out 265 sxs 60/40 pozmix - 10% gel.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/01/2003 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 700' and 1075'.
TIH with tubing to 900' - circulated cement with 200 sxs cement.
POOH. Topped with 30 sxs cement.
S.I.P. 250#.
Hooked up to annulus and pumped 35 sxs cement.
S.I.P. 350#.

RECEIVED
JUL 11 2003
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

JUL 09 2003

CHAMPLIN REFINING CO.

#4 SUTOR

13-10-20W
SE NW NE 22

Contr. CHAMPLIN REFG _____ ROOKS _____ County

E. 2201 Comm. 3-1-50 Comp. 4-21-50 IP 363 BOPD

Tops	Depth	Datum
ANH	1620	+581
HEER	3403	-1202
IANS	3442	-1241
ARB	3743	-1542
TD	3747	-1546

Casing

8" 252
5" 3744

DP 3747: TD
1000' 01H/2 HR.
SWB 29 BO/2 HRS.

BERLAND

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS



Sutor #4 SE NW NE 13-10-20W
1040 TD Fluid @ 700'
Photo 10/7/02