

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02089-00-00
Spot: SENENE Sec/Twnshp/Rge: 13-10S-20W
4290 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: EARL SUTOR Well Number: 2
County: ROOKS Total Vertical Depth: 3780 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3780
Surface Casing Size: 8.625 feet: 256

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2003 2:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JOE STRUBE Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered out 925 sxs 60/40 pozmix - 10% gel - 800# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/01/2003 3:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 700' and 1675'.
TIH with tubing to 1700' - mixed and pumped 100 sxs cement.
Pulled up to 850' - pumped 200 sxs cement.
POOH. Pumped 300 sxs cement. SIFN.
07-01-2003
Topped off with 240 sxs cement and 800# hulls.
Hooked up to annulus and pumped 85 sxs cement.
S.I.P. 200#.

RECEIVED
JUL 1 2003
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CHAMPLIN REFINING CO.

#2

EARL (SUTOR)

22-13-10-20W
SE NE NE

Contr.

ROOKS

County

E 2227 Comm. 9-29-49 Comp. 11-25-49 IP 3000 BOPD

Tops	Depth	Datum	Casing
ANH	1650	+ 577	8" 256 5" 3780
			DST 3483-50, OP 15 MIN, 120' OIL & GAS CUT. MUD PERF 24S, 3767-71 SWB 120 80/3 HRS
LANS	3159	- 1232	
ARB	3765	- 1538	
T.D.	3780	- 1553	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS



Sutor #2 SENENE 13-10s-20w
5 seconds to fluid.

Photo 10/7/02
1650' TD 500' to fluid

2212 S
137 S
650