

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02097-00-01  
Spot: NENENE Sec/Twnshp/Rge: 13-10S-20W  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: EARL C Well Number: 11  
County: ROOKS Total Vertical Depth: 3759 feet

*OB*  
*182501*

Operator License No.: 9963701 KCC Fee Fund  
Op Name: CRUDE RECOVERY CORPORATION  
Address: 1650 GEORGETOWN, STE 200  
WICHITA, KS 67218

Production Casing Size: 5.5 feet: 3757  
Surface Casing Size: 8.625 feet: 193

Well Type: EOR UIC Docket No: E18410.1 Date/Time to Plug: 06/24/2003 8:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: JOE STRUBE Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered out 315 sxs 60/40 pozmix - 10% gel.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 06/24/2003 11:30 AM KCC Agent: JAY PFEIFER

**Actual Plugging Report:**

Perforated well at 700' and 1650'.  
TIH with tubing to 1800' - mixed and pumped 100 sxs cement.  
Pulled up to 700' - circulated cement with 200 sxs cement.  
POOH. Topped with 90 sxs cement. S.I.P. 150#.  
Hooked up to the annulus and pumped 25 sxs cement with 100# hulls.  
S.I.P. 100#.

THIS IS A KCC FEE FUND PLUGGING.

**RECEIVED**  
**JUL 28 2003**  
**KCC WICHITA**

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: TBG

District: 04

*JD*

Signed Jay Pfeifer  
(TECHNICIAN)

CHAMPLIN REFINING CO.

#11 EARL

13-10-20W

22

NE NE NE

Contr. CHAMPLIN REFINING COMPANY

ROOKS

County

E. 2221 RB Comm.

Comp. 6-20-52

IP 193 BOPD

Tops	Depth	Datum
HEEB	3116	-1195
TOR	3138	-1217
LANS	3153	-1232
COG	3602	-1171
ARB	3756	-1535
T D	3759	-1538

Casing  
8" 193  
5" 3757

DST 3178-3505, 1 HR,  
25' MUD, VSSO:BHP  
200#

DST 3535-55, 30 MIN,  
445' OIL, 20' OIL  
CUT MUD:BHP 1050#

DST 3576-3600, 30 MIN,  
426' OIL, 24' OIL  
CUT MUD:BHP 400#

MARCOTTE  
POOL

DD 3759: SWB 30  
BFPH, 50% OIL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

