

X 10-19 15-163-0325020000
1951

6 031176

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C S/2 NW NW ^{8E} SEC. 13, T 10 S, R 20 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
2240 4785 feet from S section line
RT KLL 2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6854
Operator: Sohio Petroleum Co.
Name & Address: Box 4587
Houston, Texas 77210

Lease Name Sutor Well # 1 SWD ANB KLL
County Rooks 138.58
Well Total Depth 4264 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 1619

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Alt 1 completion D 2978

Plugging Contractor Halliburton License Number

Address Hays, Ks.

Company to plug at: Hour: AM Day: 19 Month: Oct Year: 19 88

Plugging proposal received from Joel Stull

(company name) Sohio Pet Co. (phone)

were: 10 3/4" set at 1619' w/1335 sks cwc 7" set at 3823' w/200 sks. 5 1/2" set at 3842'.

Plugging method o.k.'d by Wichita. Order 750 sks 65/35 Poz 10% Gel 2% Dicol and 50 sks

Common Cement. Halliburton Cemnt O.H. Arb 3823' 4236'. Hertel's Water Truck

3700' with wireline hit fluid level at 656'.

RECEIVED
STATE CORPORATION COMMISSION
12-29-88
DEC 29 1988
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00PM Day: 19 Month: Oct Year: 19 88

ACTUAL PLUGGING REPORT Squeeze 5 1/2" w/50 sks Common Cement chased w/460 sks cement

blend. To max psi 200#. Close in psi 200#, 600# Hulls added after 150 sks cement.

Squeeze annulus 7" w/50 sks to max psi 150# Close in 150# squeeze 10 3/4" annulus w/140 sks

to max psi 150# Close in 150# plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

INVOICED
DATE 1-9-89
INV. NO. 23524