

204

6 041297

API NUMBER 15- 163-03,533-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW SE SEC. 13, T 10 S, R 20 W/Ex
1650 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30323

Lease Name Sutor A Well # 6

Operator: Tex/Con Oil and Gas Co
Name & Address: 9401 Southwest Freeway
Houston, Tx. 77074

County Rooks 122.16

Well Total Depth 3759 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1622 w/800 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing License Number

Address Hays, Ks.

Company to plug at: Hour: 9:00 Day: 14 Month: May Year: 19 91

Plugging proposal received from Joel Stull

(company name) Tex-Con (phone)

were:

5 1/2 casing set at 3754 w/150 sks cement: perfs at 3230 to 3248. Perf

anhy at 1632; ordered 400 sks 60/40 poz 10% gel w/1/2 lb f.c. plus 12 sks gel:

Plugging Proposal Received by Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30 PM Day: 14 Month: May Year: 19 91

ACTUAL PLUGGING REPORT Set cement retainer at 3170; sq 50 sks cement and poz below retainer at 300 lbs p.s.i.: Spot 100 cement on top of retainer: pull up, spot gel from 3050 to 1650; perf 5 1/2 casing at 1632. Circ cement to surf. Via casing annulus and inside 5 1/2 casing pull tubing and fill to surf w/cement. 350 sks.

RECEIVED
STATE CORPORATION COMMISSION
5-30-91
MAY 30 1991

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE 6-5-91

INV. NO. 32012

J.H.S.

Signed Dennis L. Hamel (TECHNICIAN)

Dennis Hamel

CONSERVATION DIVISION
Wichita, Kansas