

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-12069-00-01
Spot: SESWS Sec/Twnshp/Rge: 13-10S-20W
330 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: SUTOR A Well Number: 7
County: ROOKS Total Vertical Depth: 3790 feet

Operator License No.: 31008
Op Name: BOWMAN, PAUL D/B/A PAUL BOWMA
Address: 801 CODELL ROAD
CODELL, KS 67663

Production Casing Size: 5.5 feet: 3738 w/150 sxs cmt
Surface Casing Size: 8.625 feet: 1612 w/800 sxs cmt

\$123¹⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/22/2003 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: PAUL BOWMAN Company: BOWMAN, PAUL OIL COMPANY Phone: (785) 434-2633

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Scout card shows 8 5/8" at 316'. Old records show 8 5/8" at 1612' w/800 sxs (12-1971).
5 1/2" set at 3738' w/150 sxs cement.
PBTD 2500'. Fluid Level 2200'.
No squeeze records. Perforations: Anhy 1650' - Dakota at 920'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/22/2003 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perf Tech perforated Anhy. at 1650' and Base of Dakota at 920'.
Ran tubing to 2500'.
Allied pumped 270 sxs 60/40 pozmix - 10% gel with 300# hulls -circulated cement out 5 1/2".
PTOH. Pumped 70 sxs cement. Circulated cement out of 8 5/8" casing.
Shut in. Squeezed Max. P.S.I. 500#. S.I.P. 500#.

RECEIVED
10-31-03
OCT 31 2003
KCC WICHITA

Remarks: WELL HAD 8 5/8" AT 1612'. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

100

Signed Richard Williams
INVOICE (TECHNICIAN)

10-31-03
2004060715

Form CP-2/3

OCT 27 2003

13-10-20W
SE SW SE

SOHIO PETROLEUM CO. #7 SUTOR A


Contr. B. W. RINE DRILLING CO. ROOKS County

R 2193 Comm. Comp. 5-5-50 IP 3000 BOPD
DRAW DOWN

Tops	Depth	Datum
ANH	1605	+588
HEEB	3400	-1227
LANS	3434	-1251
CONG	3670	-1477
SIMP	3727	-1534
ABB	3737	-1544
ID	3741	-1548

Casing
 8" 316 1085' 01H @ 3739: DU
 5" 3738 3741: 1600' 01H/2 HRS.
 ACID 500

BERLAND POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS