

15-163-02095-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 50

SE-SW-NE Sec. 13, T 10 S, R 20 W/E

— feet from N/S section line

— feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Earl 'C' Well # 8

Operator: Phillips Pet. Co.
Name & Address: Box 287
Great Bend, Ks 67530

County Rooks

Well Total Depth 3768 feet

Conductor Pipe: Size — feet —

Surface Casing: Size 8 5/8 feet 200'

Abandoned Oil Well X Gas Well — Input Well — SWD Well — D&A —

Other well as hereinafter indicated —

Plugging Contractor Kelso Casing License Number —

Address Chase, Kansas

Company to plug at: Hour: PM Day: 18 Month: 1 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Bill Fulls

(company name) Kelso (phone) —

were: 5 1/2" @ 3764' - P.B.T.D @ 3704' - Perfs @ 3496-98,
3516-18, 42-47, 52-58, 62-68, 94-98; 3614-16, 49-53, 66-68.
P.B. w/5 sx cmt -> sand to 3475' -> 45 sx cmt.
Ordered 200 sx 50 ppg 60 gel - 20 gel - 5 hulls.

Signed Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part — None —

Operations Completed: Hour: 2:00 PM Day: 18 Month: 1 Year: 19 83

ACTUAL PLUGGING REPORT Plugged through esq. -> slot @ 1245' + pumped
25 cmt -> 25 cmt w/hulls -> 4 gel -> disp to 1000' w/water -> slot @
926' + pumped 3 gel -> 50 cmt w/hulls -> 3 gel -> disp w/water
to 500' -> slot @ 728' + pumped 2 hulls -> 3 gel -> 50 cmt ->
3 gel -> disp to 100' w/water - slot @ 535' -> slot @ 201' ->
pumped in 1 hull -> 4 gel -> 50 cmt -> Recovered 201' of

Remarks: 5 1/2" casg. no P.S.I. ->

I hereby certify that the above plugging instructions were given as herein stated and that I (did) (did) did not) observe this plugging.

INVOICED
2-8-83
2379-W

RECEIVED
STATE CORPORATION COMMISSION
01-31-83
JAN 31 1983
CONSERVATION DIVISION
Wichita, Kansas

Signed Dennis L. Hamel
(TECHNICIAN)