

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02093-00-00  
Spot: NWNENE Sec/Twnshp/Rge: 13-10S-20W  
4950 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: EARL Well Number: 6  
County: ROOKS Total Vertical Depth: 3744 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3739  
Surface Casing Size: 8.625 feet: 245

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/24/2003 12:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: JOE STRUBE Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered out 395 sxs 60/40 pozmix - 10% gel.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 07/01/2003 4:00 PM KCC Agent: JAY PFEIFER

**Actual Plugging Report:**

Perforated casing at 700' - 1675' - 2150'.  
TIH with tubing to 2200' - mixed and pumped 100 sxs cement.  
Pulled up to 700' and circulated cement with 200 sxs cement.  
POOH. Topped off with 70 sxs cement.  
S.I.P. 100#.  
Hooked up to annulus and pumped 25 sxs cement.  
S.I.P. 100#.  
07-01-2003 - Topped 5 1/2" with 50 sxs cement.

RECEIVED  
JUL 11 2003  
KCC WICHITA

Remarks: COPELAND ACID & CEMENTING.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)


CHAMPLIN REFINING CO. #5 EARL ~~Sutton~~ 13-10-20W 22  
NW NE NE

Contr. \_\_\_\_\_ ROOKS County

E 2206 Comm. 3-26-50 Comp. 5-19-50 IP 343 BOPD  
PHY POT

Tops	Depth	Datum	Casing
ANH	1620	+586	8" 245 DP 3744
HCFD	3101	-1198	5" 3739 SWB 8 1/2 BOPH
I ANS	3112	-1236	
CONG	3681	-1475	
SIMP	3717	-1511	
ARB	3738	-1522	
T.D.	3744	-1538	

BERLAND POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS



Sutor #6 NW NE NE 13-10s-20w  
Swedged  
3538' to TD Fluid @ surface  
Oil spill @ well head 1/10 Bbl.  
Photo taken 10/7/02