

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-02101-00-00  
Spot: CSWNWNW Sec/Twnshp/Rge: 13-10S-20W  
4290 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: SUTOR A Well Number: 7  
County: ROOKS Total Vertical Depth: 3721 feet

Operator License No.: 32500  
Op Name: T & P OIL & GAS, L.L.C.  
Address: 7801 METCALF  
OVERLAND PARK, KS 66204

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 304 **\$120.93**  
Production: Size 5.5 feet: 3717  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/18/2001 9:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: WALLY WAHLMEIER Company: PROFESSIONAL PULLING SERVIC Phone: (785) 628-7443

Proposed Plugging Method: According to KCC Rules & Regulations.  
Ordered 350 sxs cement and 800# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 12/18/2001 12:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 2700'.  
Pumped 100 sxs cement with 500# hulls.  
Pulled tubing to 1725' - circulated with 150 sxs cement and 300# hulls.  
Pulled all tubing and topped off with 35 sxs cement to Max. P.S.I. 200#. S.I.P. 200#.  
Annulus took no cement.  
Total of 250 sxs 60/40 pozmix - 10% gel - 800# hulls.

Remarks: SWIFT CEMENTING. KELLER TANK-WATER.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

Roger L. Moses  
(TECHNICIAN)

RECEIVED

1-4-02  
JAN 04 2002

KCC WICHITA

INVOICED

DATE 01-07-02

INV. NO. 2002061201

Form CP-2/3

JAN 03 2002

PETROLEUM, INC

#7 SUTOR 1A

13-10-20W

SW NW NW

Contr. GARVEY DRLG

ROOKS

County

E 2180<sup>RS</sup>

Comm.

Comp.

2-22-57

IP 121 SOPD

| Tops | Depth | Datum |
|------|-------|-------|
| ANH  | 1610  | 570   |
| HEEB | 3388  | -1208 |
| TOR  | 3408  | -1228 |
| LANS | 3421  | -1241 |
| B/KC | 3638  | -1458 |
| CONG | 3655  | -1475 |
| SIMP | 3694  | -1514 |
| ARB  | 3715  | -1535 |
| TD   | 3721  | -1541 |

Casing

8" 304

5" 3717

DST 3492-3545/45", 30' MUD, BHP 790#  
 DST 3540-3615/1 HR, 120' G, 180' O & GCM  
 30' HO & GCM, BHP 500#  
 DST 3716-21/1 HR, 90' G, 90' HO & GCM,  
 120' H MDY O, 240' WC MDY O, 1020' O  
 BHP 960#  
 CO TD: SWB 6 BOPH, WW/9 HRS

MARCOTTE

|  |  |  |
|--|--|--|
|  |  |  |
|  |  |  |
|  |  |  |

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS