

10-29 15-163-00651-0000

API NUMBER 15- 1-1950

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6 041253

NE NE NW, SEC. 13, T 10 S, R 20 W/E
4950 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5238
Operator: Pet. Inc.
Name & Address: Box 186
Plainville, Ks. 67663

Lease Name Sutor Well # 1
County Rooks 122.62
Well Total Depth 3773 feet
Conductor Pipe: Size feet
Surface Casing: Size 85/8 feet 316 w/100 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B.I. Titan License Number
Address Hays, Ks.

Company to plug at: Hour: 1:00 PM Day: 29 Month: Oct Year: 19 90

Plugging proposal received from Everett Jones
(company name) P. I. (phone)

were: 5 1/2 casing set at 3769 w/100 sks cement; perfs at 3612 to 3680;
Perf anhy at 1640; perf base dakota at 480. D.V. at 1640 circ w/400 sks.

Ordered 350 sks 65/35 poz 10% gel w/1/4 lb f.c. plus 500 lbs. hulls.

Plugging Proposal Received by Dennis Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30PM Day: 29 Month: Oct Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 5 1/2 casing w/315 sks cement w/1/4 lb f.c.
plus 400 sks hulls mixed in cement. Max 1000 lbs. S.I. 600 lbs.

Pumped in 8 5/8 casing w/35 sks cement w/1/4 lb f.c. and 100 lbs hulls mixed in cement.
Max 1000 lbs. S.I. 600 lbs.

RECEIVED
STATE CORPORATION COMMISSION
11-30-90
NOV 30 1990

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
I did/did not observe this plugging.

DATE 12-7-90
INV. NO. 30174

Handwritten initials

Signed Dennis L. Hamel
(TECHNICIAN)