

TO:
STATE CORPORATION COMMISSION ·
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23385-00-00
Spot: NW Sec/Twnshp/Rge: 13-10S-20W
4065 feet from S Section Line, 4150 feet from E Section Line
Lease/Unit Name: SUTOR B Well Number: 9
County: ROOKS Total Vertical Depth: 3785 feet

Operator License No.: 32500
Op Name: T & P OIL & GAS, L.L.C.
Address: 7801 METCALF
OVERLAND PARK, KS 66204

Surface Casing Size: 8.625 feet: 221

123'

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/20/2003 8:30 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: ED MCKENNA Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
No ar buckle found.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 09/20/2003 10:30 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 1650' w/25 sxs. Anhydrite 1625' - 1670'.
2nd. Plug at 950' w/100 sxs. Dakota 630' - 930'.
3rd. Plug at 275' w/40 sxs. Surface pipe to 221'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.


RECEIVED
09-25-03
SEP 25 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed


(TECHNICIAN)

INVOICED

DATE 9.25.03

INV. NO. 2004060542

Form CP-2/3

SEP 23 2003