

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02100-00-00
Spot: CNWSWNW Sec/Twnshp/Rge: 13-10S-20W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: SUTOR A Well Number: 6
County: ROOKS Total Vertical Depth: 3759 feet

Operator License No.: 32500
Op Name: T & P OIL & GAS, L.L.C.
Address: 7801 METCALF
OVERLAND PARK, KS 66204

Conductor Pipe: Size feet: 8/22.17
Surface Casing: Size 8.625 feet: 299
Production: Size 5.5 feet: 3756
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/18/2001 12:45 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: WALLY WAHLMAIER Company: PROFESSIONAL PULLING SERVIC Phone: (785) 628-7443

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 155 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 12/18/2001 1:40 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: ROGER MOSES

Actual Plugging Report:

Squeezed with 400 sxs common with 2% c.c.
Drilled plug to 1485'.
Alt. II with unknown cement amount.
Tied to casing and pumped 110 sxs cement and 500# hulls.
Max. P.S.I. 1000#. S.I.P. 600#.
Total 110 sxs 60/40 pozmix with 10% gel and 500# hulls.

Remarks: SWIFT CEMENTING. KELLER TANK-WATER.

Plugged through: CSG

District: 04

Signed

Roger H. Moses
(TECHNICIAN)

RECEIVED
1-4-02
JAN 04 2002
KCC WICHITA

INVOICED

DATE 01-07-02

INV. NO. 2002061201

Form CP-2/3


JAN 02 2002

PETROLEUM, INC. #6 SUTOR 1A 13-10-20W
 NW SW NW
 Contr. GARVEY DRILG ROCKS County
 E 2180^{ss} Comm. Comp. 12-7-56 IP 160 BOPD

Tops	Depth	Datum
ANH	1600	580
HEEB	3386	-1206
TOP	3408	-1228
LANS	3421	-1241
B/KC	3636	-1456
CONG	3667	-1487
ARB	3725	-1545
TD	3759	-1579

Casing
 8" 299
 5" 3756
 DST 3542-3610/1 HR, 300' G, 120' MDY O, 300'
 300' HO & GCW, BHP 650#
 DST 3668-90/40", 10' M, BHP 300#
 DST 3725-29/1 HR, 1890' O & GC SW, BHP
 1120#
 DST 3739-59/30", 2,010' SW, BHP 920#
 STRAD DST 3647-3725/1 HR, 860' SW, BHP
 525#

BERLAND
 CO 3732: PERF 12/3611-13
 16/3716-20: SWB 4 BOPH/4
 HRS, 600' OB



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS