

4-041865

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-9

API Number: 15-163-20,900-0000

NW SW SE /4 SEC. 15, 10 S, 20 W
990 feet from S section line
2310 feet from E section line

Operator license# 5030

Lease: Marcotte Well # 10

Operator: Vess Oil Corporation

County: Rooks 120.31

Address: 8100 E. 22nd. St. N. Bldg 300
Wichita, Kansas 67226

Well total depth 3702 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 282 feet
w/ 200 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing, Inc. License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 9 Month: December Year 1996

Plugging proposal received from: Joel Stull

Company: Vess Oil Corporation Phone: 913-885-4352

Were: 5 1/2" casing set at 3698' w/200 sxs.
O.H. 3698' - 3702'; Perfs. 3211' - 3630'. Stage collar at 1582' w/400 sxs. cement.
PBD 3702'.
Ordered 225 sxs 60/40 pozmix - 10% gel with 1/4# F.C. - 500# hulls - 13 sxs gel.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:00 P.M., Day: 9, Month: December, Year: 1996

Actual plugging report: 5 1/2" casing squeezed as follows: 50 sxs w/300# hulls, followed with 13 sxs gel, followed with 150 sxs w/200# hulls Max. P.S.I. 500#. S.I.P. 200#. 8 5/8" S.P. - pressured-up 600# w/5 sxs cement.

12-30-96

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X NO
Plugged through TUBING, CASING Elevation: 2170 K.B.

I did not observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED
DATE JAN 03 1997

WV. NO. 47258

12-9