

4-071104

7-22 15-163-02168-0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 8-20-44

SE SW SE /4 SEC. 15, 10 S, 20 W  
330 feet from S section line  
1560 feet from E section line

Operator license# 5030

Lease Marcotte well # 3

Operator: Vess Oil Corporation

County Rooks

Address: 8100 E. 22nd Street  
North Building #300  
Wichita, Kansas 67226  
Mike Kasselmann

Well total depth 3745 feet <sup>112.93</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 167 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas and Hays, Kansas

Company to plug at: Hour: A.M. Day: 22 Month: July Year: 94

Plugging proposal received from: Mike Kasselmann

Company: Vess Oil Corporation Phone: 316-682-1537

Were: 8 5/8" - 167' S.P. cwc w/75 sxs. cement. 4 1/2" casing set @ 3734' w/125 sxs. cement. 2 7/8" liner set 0 to 3715' cwc. w/200 sxs. 4 1/2" squeezes - @ 1029' w/250 sxs. cement. - @ 1490' w/300 sxs. cement - @ 885' w/150 sxs. cement - @ 1560' w/20 sxs. cement - @ 885' w/250 sxs. cement. Proposal 175 sxs. 60/40 pozmix - 10% gel and 4 sxs. hulls. Pumped in with pump truck - load 2 7/8" casing bull squeeze top to bottom. Shut in under pressure - also squeeze 4 1/2" x 8 5/8" annulus with cement. Shut in under pressure.

Plugging Proposal Received by: Dennis Hamel - Marion J. Schmidt  
Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 12:00P.M., Day: 22, Month: July, Year: 94

Actual plugging report: Vess Oil ordered 150 sxs. 60/40 pozmix - 10% gel and 4 sxs. hulls. Pumped in with pump truck.

1) Pumped in 2 7/8" casing w/96 sxs. cement w/.5 sx. hulls - 1000# P.S.I. Shut in 450# P.S.I.

2) Squeezed 4 1/2" x 8 5/8" annulus w/75 sxs. cement with 1 sx. hulls. 400# P.S.I. 100# P.S.I. shut in.

Remarks: Cemented by Allied Cement.  
Condition of casing(in hole): GOOD X BAD      Anhy.plug: YES X NO       
Bottom plug(in place): YES X, CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING X. Elevation: 2185 GL

I did NOT observe the plugging.

*Marion J. Schmidt*  
(agent)

DATE 8-15-94

WV. NO. 40947

SEP 28 1994