

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-02164-00-00
Spot: CNWNWNE Sec/Twnshp/Rge: 15-10S-20W
330 feet from N Section Line, 2310 feet from E Section Line
Lease/Unit Name: BRUEGGEMAN Well Number: 7
County: ROOKS Total Vertical Depth: 3785 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3783 150 SX CMT
Surface Casing Size: 8.625 feet: 165 100 SX CMT

\$123.01

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/29/2003 2:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 225 sxs SMD and 500# hulls.
Perfs 3783'-3786' open hole.
February 11, 1991 - Packer 3667' - could not pull - POH with 118 joints.
2 7/8" tubing - Hunted holes 580' - 1600'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 04/29/2003 5:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 2416' - pumped 160 sxs SMD with 500# hulls - cwc to surface.
Pulled tubing and tied onto 5 1/2" casing - pumped 15 sxs SMD.
Max. P.S.I. 500#. S.I.P. 500#.
Tied onto 8 5/8" - pumped 30 sxs on backside.
Max. P.S.I. 100#. S.I.P. 100#.

RECEIVED
MAY 05 2003
KCC WICHITA
05-05-03

Remarks: SWIFT SERVICES, INC.-TICKET #5505.

Plugged through: TBG

District: 04

FD

Signed

Pat Staab

(TECHNICIAN)

INVOICED

DATE 5-6-03

AMOUNT 2003061500

Form CP-2/3

MAY 01 2003

CHAMPLIN REFINING COMPANY #7 BRUEGGEMAN 15-10-20W 22
 NW NW NE

Contr. _____ ROOKS County

E 2237RB Comm. _____ Comp. 6-6-52 IP 337 BOPD
 PHY POT

Tops	Depth	Datum
Amh	1680	
HEEB	3460	-1223
LANS	3498	-1261
CONG	3748	-1511
SIMP	3762	-1525
ARB	3782	-1545
T.D.	3785	-1548

Casing

8" 156 DST 3677-3702, 1/2 HR,
 5" 3783 120' H OIL & GAS
 CUT MUD & MUDDY OIL
 BHP 680#:
 DP: SWB 18 BOPH

MARCOTTE POOL

+	+	+	+
+	+	+	+
+	+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS