

6

040902

5-17-88

217 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-01138-0001

SW SW NE, SEC. 21, T 10 S, R 20 W/EX

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5051

Lease Name _____ Towns _____ Well # 1

Operator: Hellar Drilling
Name & Address: 711 Pet Bldg.
Wichita, Ks. 67602

County _____ Rooks 121.02

Well Total Depth 3724 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 272' w/175

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cement License Number _____

Address Russell, Ks.

Company to plug at: Hour: 9:00As Day: 17 Month: June Year: 19 88

Plugging proposal received from Carl Gilpin

(company name) Hellar Drilling (phone) _____

were: 5 1/2" casing set at 3723' w/125 sks cement.

Perfs at 3231' to 3239'. Perf casing for plugging at 1685' and 950' 3 holes each.

Ordered 300 sks 65/35 Poz 10% Gel w/1/4# F.C. plus 10 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30AM Day: 17 Month: June Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 150 sks cement w/1/4# F.C. plus 5 sks Hulls mixed

in cement. Max Psi 1000# Shut in 900# . Pumped in 8 5/8" casing 20 sks cement w/1/4# F.C.

Max Psi 900# Shut in 500#.

RECEIVED
STATE CORPORATION COMMISSION
7-6-88
JUL 6 1988

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Dennis L. Hamel
Dennis Hamel (TECHNICIAN)

DATE 7-12-88

INV. NO. 21277

6-17