

4-041994

11-10

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-22,005 (7-9-81)

C W2 W2 NW /4 SEC. 20, 12 S, 18 W
3960 feet from S section line
4950 feet from E section line

Operator license# 100

Lease: Joy Well # 1

Operator: Kansas Corporation Commission
State of Kansas Fee Fund
Address: 2301 E. 13th Street
Hays, Kansas 67601
Control #990033-001

County: Ellis 123,21

Well total depth 3791 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 214 Feet
W/N/A sxs.cmt.

Aband. oil well ☒ Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 20 Month: October Year 1998

Plugging proposal received from: Kansas Corporation Commission - Dist. #4 Staff

Company: Kansas Corporation Commission Phone: 785-625-0550

Were: 5 1/2" casing set at 3790' w/N/A sxs cement.

Ordered 250 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION
12-1-1998
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:00 P.M. Day: 10, Month: November Year: 1998

Actual plugging report: Ran into bridge at 754' at base of Dakota. Could not drill through. Rigged up washover pipe with shoe. Tried to get over and fish but could not get ahold of much. Cleaned to 1100' at base of Cedar Hill. Broke pin on bottom joint of wash pipe. Cost to fish more than to bury. Since well at minimum plug depth decided to plug. R.I.H. with tubing. Tagged T.O.F. at 1102'. Pulled up to 1100' - pumped 110 sxs cement to circulate at surface. P.O.O.H. and squeezed casing with 100 sxs cement with 200# hulls. Max. P.S.I. 500#.
8 5/8" S.P. - Squeezed 35 sxs cement. Max. P.S.I. 200#. S.I.P. 200#.

Remarks:

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plugin: YES ☒ NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES ☒ NO _____
Plugged through TUBING _____ CASING _____ Elevation: _____ G.L. _____

I did[X] / did not[] observe the plugging.

Dennis Hamel
(agent)

Form CP-2/3