

6 030759

15-051-21709-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 6-21-79

NWNWNE SEC. 8, T. 12 S., R. 19 W

4950 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6114

Lease Name SPREEN Well # B 1-8

Operator: DON E. PRATT

County ELLIS 123.44

Name & Address P.O. Box 370

Well Total Depth 3798 feet

HAYS, KANSAS

Conductor Pipe: Size _____ feet

67601

Surface Casing: Size 8 5/8 feet 128'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON License Number _____

Address HAYS, KANSAS 67601

Company to plug at: Hour: PM Day: 2 Month: 7 Year: 19 86

Plugging proposal received from Marvin Miller

(company name) DON E. PRATT (phone) _____

were: 8 5/8 SET @ 128' w/ 90SX. 5 1/2 SET @ 3798 w/ 175SX. PBTD 3797

PERF. 3625-28 ORDER SAND & COM. CMT. PULLPIPE ORDER

200SX. ECINOLITE CMT. 5SX. HULLS HALLIBURTON CMT. CO.

COMPANY WATERTRUCKS

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30PM Day: 2 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBTD FROM 3797 TO 3570' SPOT

5SX. COMCMT ON SAND W/BAILER & HOT & RECOVERED 2488' OF 5 1/2'

TIE ON TO 8 5/8 MIX. & PUMP 3SX. HULLS - 200SX. CMT. MIX. + 2SX.

HULLS. MAX. PST. 800# CLOSE IN 300# PLUG COMP.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

23
1-30-86

INVOICED

(If you do not observe this plugging.

DATE AUG - 6 1986

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 14622

AUG 4 1986
8-4-1986