

6 070665

4-19-88 15-163-00299-0000 456

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 4-13-51

SW  
NE SW SW, SEC. 22, T 10 S, R 20 W/E  
21 KCC  
\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT 6593

Operator License # Coastal Oil & Gas

Lease Name Roger Well # A-1

Operator: 211 N. Robinson #1700

County Rooks 121.03

Name & Address Oklahoma City, Ok 73102

Well Total Depth 3724 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 190'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ U&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B. J. Titan License Number \_\_\_\_\_

Address \_\_\_\_\_ hays, Kansas 67601

Company to plug at: Hour: 10:00 am Day: 19 Month: April Year: 19 88

Plugging proposal received from Don De Herrah

(company name) Coastal Oil and Gas Corp. (phone) (316)697-2137

were: 8 5/8" 190' SP cu w/ 125 sx cmt, 4 1/2' casing set @ 3720 w/100 sx cmt. Perfs @ 3720-24'

No known squeeze, no DV tool, no pipe recovery. Proposal 225 sx 65/35 Poz. 10% gel.

2% additive and 5 sk hulls. Perf 4 1/2" casing @ 869' and 1720' with pump truck

load both 4 1/2" casing and annulus with cement. Shut in under pressure. Later

discovered 4 1/2" casing perf at 1000'.

Plugging Proposal Received by \_\_\_\_\_

Marion Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:45 pm Day: 19 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Ordered 225 sx 65/35 Pozmix 10% Gel, 2% additive, and 5 sx hulls.

Pumped in with pump truck. Perf @ 869' and 1720'. Annulus open pumped in 4 1/2" casing

25 sx cement followed with 200 sx cement w/ 5 sx hulls mixed in. Annulus did not

circulate. Returned with another 200 sx econolite, pumped in 4 1/2" casing

another 75 sx cement, 400 psi max, 200 psi shut in. Pumped 10 sx cement in annulus

450 psi max. Shut in @ 300 psi. BJ Titan

Remarks: RECEIVED STATE CORPORATION COMMISSION  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-21-88

INV. NO. 20899

CONSERVATION DIVISION  
Wichita, Kansas

Signed Marion Schmidt (TECHNICIAN)

Marion Schmidt