

6 070472

163-21, 677-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

NE-NE-SE, SEC. 22, T 10 S, R 20 W

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Lease Name Sutor Well # 12

Operator: Champlin Pet. Co
Name & Address: 6441 NW Grand Blvd
#300, Okla City, Ok
73116-2298

County Pooko 126.75

Well Total Depth 3900 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cmt Co. License Number

Address East Hwy 40, Hays, Kans. 67601

Company to plug at: Hour: 3:00 PM Day: 4th Month: april Year: 1986

Plugging proposal received from B. F. Hartnett

(company name) Champlin Pet (phone) 913-434-2685

were: 8 5/8" - 226 ft 50 cmt / 200 cmt, 5 1/2" set @ 3899 ft. / 250 cmt.

RBD - 3822', Perf. 3818 - 3558-72

Squeezed 5 1/2" @ 3788-92" / 50 cmt and 3530" - 3636" / 250 cmt.

and 1671" / 375 cmt circulated w/cement - 20 cmt extra

Prepared. Order 200 cmt (Eccordite) 200 65% Formix, 10% Gel,

2% Eccordite, 1/4" flo Cils per sack

Pressure stimulus w/cement Received by [Signature] (TECHNICIAN)

Plugging Operations attended by Agents: All Part None

Operations Completed: Hour: 3:00 PM Day: 4th Month: april Year: 1986

ACTUAL PLUGGING REPORT Ordered 120 65% Formix, 10% Gel, 2%

Eccordite (additive) 1/4" flo. Cils per sack.

Pumped in Annulus between 8 5/8" and 5 1/2" csg

3 cmt, Max Pressure 600 Psi.g

Pumped in 5 1/2" Csg 155 cmt w/ 3 shells mixed

in, max pressure 1200 Psi.g Shut In @ 150 Psi.g

Remarks: By Halliburton Cmt

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging

STATE CORPORATION COMMISSION

[Signature] (TECHNICIAN) 4-11-86

DATE APR 15 1986

APR 13 1986

INV. NO. 13400

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84