

15-163-02175-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SW, Sec. 22, T 10 S, R 20 W/E

990 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6593

Lease Name Rogers Well # A#2

Operator: Coastal Oil & Gas
Name & Address P.O. Box 1117,
Elkhart, Mo.

County Rooks

Well Total Depth 3691 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 202'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 176, Chase, Mo. 64524

Company to plug at: Hour: 10:00 AM Day: 19 Month: 10 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Mike Kelso.

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Order out sacks 50 permix-6% Gel, 17 sacks Gel, 2 sacks hulls.
Run tubing to bottom to spot cement.

Signed [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 PM Day: 19 Month: 10 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 202' SP. cnc. w/ 150 sacks common. 5 1/2" set at 3687' w/ 100 sacks common. 4' of open hole. Ordered out 250 sacks 50 permix-6% Gel, 17 sacks Gel, 2 sacks hulls. Ran tubing to 3219' & spotted 20 sacks cement, Pulled tubing to 2900' & spotted 17 sacks Gel, Pulled tubing to 1550' & spotted 60 sacks cement, Pulled tubing to 800' & spotted 110 sacks cement to surface. Pumped 60 sacks in 8 5/8"

Remarks: Maximum pressure 300 pounds
Packer in hole at 3219'

I hereby certify that the above plugging instructions were given as written and that I (did / did not) observe this plugging.

STATE CORPORATION COMMISSION
RECEIVED
NOV 1 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed [Signature]
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED
DATE 11-5-82
INVT. NO. 1491-W