

4-041742

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-22

API Number: 15- - N/A

NE NE NE /4 SEC. 06, 12 S, 20 W
330 feet from S section line
330 feet from E section line

Operator license# 4220

Lease: Armbruster "A" Well # 1

Operator: Roberts Bro. Oil Company

County: Ellis

Address: Box 1252
Hays, Kansas 67601
Dennis Roberts

Well total depth 3900 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 249 feet
w/165 sxs

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 22 Month: December Year 1995

Plugging proposal received from: Dennis Roberts

Company: Roberts Bro. Oil Company Phone:

Were: 5 1/2" casing set at 3900' w/125 sxs cement. Perf salt at 2150' - Anhy. at 1625'.
Squeeze at 940' with 165 sxs. Pulled tubing and rods 12-21-95.
Ordered 200 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls - plus 12 sxs gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:00 P.M., Day: 22, Month: December, Year: 1995

Actual plugging report: Perf. 5 1/2" casing at 1625' and 2150'. Squeezed casing with 25 sxs cement with 200# hulls, followed with 12 sxs gel, followed with 150 sxs cement with 200# hulls. Max. P.S.I. 1500#. S.I.P. 1000#. Pumped down 8 5/8" S.P. to instant pressure Max. 1000#.

KANSAS CORPORATION COMMISSION
JAN 03 1996
1-3-1996
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

INVOICED
DATE 12-29-95
INV. NO. 44354

