

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051-23,897  
NE NE SW Sec. 5, T 12 S, R 20 W  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6176

Lease Name Urban Well # 1

Operator: Ivan Holt Well Service  
Name & Box 401  
Address Russell, Ks. 67665

County Ellis

Well Total Depth 3923 feet 127.50

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 248-200 sks

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Revlin Drilling License Number 5671

Address Box 293, Russell, Ks. 67665

Company to plug at: Hour: \_\_\_\_\_ am Day: 4 Month: June Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Paula Gibson

(company name) Revlin Drilling Company (phone) (913) 483-5355

were: Order 180 lbs. 50/50 pozmix 6% gel 3% cal. cl., 1 sk flo-cel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Signed Gilbert P. Leiker  
(TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:45 PM Day: 4 Month: June Year: 1984

ACTUAL PLUGGING REPORT

1st plug @ 1700 w/25 sks

2nd plug @ 940 w/100 sks 1 sk flo-cel

3rd plug @ 260 w/40 sks

4th plug @ 40 w/8 5/8" plug 1/2 sk hulls 10 sks

10 sks in Rat Hole Cemented by Allied

Gil Balthazor witnessed the plugging.

Remarks: \_\_\_\_\_

STATE CORPORATION COMMISSION  
RECEIVED  
JUN 11 1984  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED

Signed Gilbert P. Leiker  
(TECHNICIAN)

Gilbert Balthazor

DATE 6-15-84  
INV. NO. 2030  
6-4