

4-020023 8-16
15-051-24847-00-00
API number: 15-051-24,847

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW CW2 SE /4 SEC. 02 , 12 S, 20 W
1200 feet from S section line
2040 feet from E section line

Operator license# 30606

Lease: T. Hall Well # 1-2

Operator: Murfin Drilling Co., Inc.

County: Ellis

Address: 250 N. Water
Suite 300
Wichita, Kansas 67202

Well total depth 3935 feet ^{127.88}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 1/2 Inch @ 261 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling Co., Inc. License# 30606

Address: 250 N. Water, Suite 300, Wichita, Kansas 67202

Company to plug at: Hour: Day: 8 Month: August Year: 1993

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling Co., Inc. Phone: 316-267-3241

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 3822 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1600 feet with 25 sacks

3rd plug @ 840 feet with 100 sacks

4th plug @ 310 feet with 40 sacks

5th plug @ 40 feet with 10 sacks

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 12:15, Day: 16, Month: August, Year: 1993

Actual plugging report: Hole reported plugged as above.

Order 215 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 2186 GL

I did[] did not[X] observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1993
Ken Kuhn
(agent)
OH
CONSERVATION DIVISION
Wichita, Kansas
Form CP-2/3

INVOICED
DATE AUG 30 1993
INV. NO. 38509