

4-020110

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API number: 15-051-24,933-0000  
234' SE of  
NE NE NW / 4 SEC. 02 , 12 S, 20 W  
4800 feet from S section line  
2790 feet from E section line

Operator license# 06569

Lease: Hall Well # 2

Operator: Carmen Schmitt, Inc.  
Address: P.O. Box 47  
3111 10th. St. #200  
Great Bend, KS 67530-0047

County: Ellis <sup>121.22</sup>  
Well total depth 3730 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 213 feet

Aband. oil well \_\_\_\_\_, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A X

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: 250 N. Water, Suite 300, Wichita, Ks 67202

Company to plug at: Hour: \_\_\_\_\_ Day: 11 Month: July Year: 1996

Plugging proposal received from: Keith Van Pelt

Company: Murfin Drilling Company, Inc. Phone: 316 267 3241

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 3690 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1510 feet with 25 sacks

3rd plug @ 730 feet with 100 sacks

4th plug @ 260 feet with 40 sacks

5th plug @ 40 feet with 10 sacks

RECEIVED  
KANSAS CORPORATION COMMISSION  
7-15-1996  
JUL 15 1996

Plugging Proposal Received by: Ken Kuhn

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

CONSERVATION DIVISION  
WICHITA, KS

Completed: Hour: 6:15 AM, Day: 11, Month: July, Year: 1996

Actual plugging report: Hole reported plugged as above.

Order 215 sx 60/40 pozmix w/ 6% gel and 2.0 sx celloflake or flowcel.

Remarks: Allied Cementing performed the cement job.

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES X, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING \_\_\_\_\_, CASING X Elevation: 2083 GL

INVOICED  
I did not [ X ] observe the plugging.

Ken Kuhn  
(agent)

DATE 7-23-96

WV. NO. 46064

7-11 SEP 27 1996