

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE-SE-SE, Sec. 7, T 12 S, R 20 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
330' feet from N(S) section line
330' feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5727 Lease Name U.P. SHAGGS Well # 1

Operator: ARNOTT OIL COMPANY County ELLIS
Name & Address P.O. BOX 363
PLAINVILLE, MS.
67663 Well Total Depth 4058 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8" feet 215

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor ALLIED CEMENT COMPANY License Number _____

Address BOX 31 - 332 W. WICHITA, RUSSELL, KANSAS 67665

Company to plug at: Hour: 9:30 AM Day: 2ND Month: DEC Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO ROY ARNOTT.

(company name) ARNOTT OIL COMPANY (phone) 913-434-2869

were: 8 5/8" - 215 FE. SB. CUL -> 4 1/2" SET @ 4029 FE +/- 150ST CMT.

NO PLUG. BACK - PERFS TOP 3626 FE AT. BOTTOM - 4ST CMT. SAND

TO 3575 FE +/- 4ST CMT. - SHOT CSG (2) RECOVERED 2350 FE

ORDER 165ST 50/50 Formix 4% GEL - 3% CA-CL -> 22ST GEL -> 5ST HULL'S + 8 5/8" PLUG.

PUMP IN 8 5/8" - 25ST CMT. -> 4ST HULL'S -> 15ST GEL -> 1ST HULL'S -> 70ST CMT.

7ST GEL -> REL. PLUG. AND 70ST CMT. Signed Marion J. Shredt
(TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:45 PM Day: 2ND Month: DEC. Year: 1982

ACTUAL PLUGGING REPORT ORDERED - 165ST 50/50 Formix 4% GEL - 3% CA-CL - 22ST GEL.

5ST HULL'S AND 8 5/8" PLUG. (PUMPED IN WITH PUMP. TRUCK.)

PUMPED IN - 25ST CMT. -> 4ST HULL'S -> 15ST GEL -> 1ST HULL'S

70ST CMT. (BLEW OFF PLUG. CONTAINER) LEFT OUT GEL. AND.

PUMPED IN 140ST CMT. (AFTER RELEASING. PLUG.)

MAX. PRESSURE 750 PSE (CEMENTED BY ALLIED CMT.)

Remarks: _____
RECEIVED
STATE CORPORATION COMMISSION
12-21-1982
DEC 21 1982

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 12-28-82
CMT. NO. 2025-W

Signed Marion J. Shredt
(TECHNICIAN) DOIC