

6 031389

API NUMBER 15- 051-23,915

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C N/2 NW SE, SEC. 5, T 12 S, R 20 W/EX

2310 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7383

Lease Name Hamburg Well # 1

Operator: Grady Bolding Corp

County Ellis 128.41

Name & Address 3111 10 St. Box 244

Well Total Depth 3951 feet

Great Bend, Ks. 67530

Conductor Pipe: Size feet

Surface Casing: Size 5/8 feet 252

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pulling License Number

Address Great Bend

Company to plug at: Hour: PM Day: 10 Month: July Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing (phone)

were: 8 5/8 set at 252 w/160 sks cwc. 4 1/2 set at 3949 w/150 sks.

Perf 3895 - 3905. Order sand and common cement. Pull pipe. Order 250 sks

65/35 poz 8% gel 500 lbs. hulls. Allied Cement Co. Werth Water Truck.

Plugging Proposal Received by Carl Goodrow

RECEIVED  
STATE CORPORATION COMMISSION  
7-17-1990  
JUL 17 1990  
CONSERVATION DIVISION  
Wichita, Kansas  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:00 PM Day: 10 Month: July Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 3850 w/4 sks common cement on sand w/bailer.

and recovered 260 casing. Sq 8 5/8 w/250 sks cement blend to max psi 900 lbs.

Close in psi 400 lbs.

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

(I did / did not observe this plugging.)

DATE 7-24-90

Signed Carl Goodrow

INV. NO. 28711

Tab. S.

(TECHNICIAN)  
Carl Goodrow