

15-051-20873-00-01

4-041769

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

4-30

API Number: 15-051-20,873

SE NW NW /4 SEC. 05, 12 S, 20 W
4290 feet from S section line
4290 feet from E section line

Operator license# 6246

Lease: 'Calvert' Deutscher Well # 1 OWWO

Operator: Bennett & Schulte Oil Co.

County: Ellis

Address: 112 W. 7th Street
Russell, Kansas 67665

Well total depth 3800 ^{123.50} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 245 feet
w/150 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00 A.M. Day: 30 Month: April Year 1996

Plugging proposal received from: Reginal Bennett

Company: Bennett & Schulte Oil Company Phone:

Were: 5 1/2" casing set at 3820' w/125 sxs cement. Perf. at 3701' - 3820'.
Ordered 250 sxs. 60/40 pozmix -10% gel plus 500# hulls.
Operator stated that a D.V. tool was in place at 1635' and cement circulated to surface with 350 sxs. Tubing fish at 1240'.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:45 P.M., Day: 30, Month: April, Year: 1996

Actual plugging report: Rig-up cementers to 8 5/8" S.P. Casing annulus. Pumped in 50 sxs cement with 100# hulls. Max. P.S.I. 500#. R.U. Cementers to 5 1/2" casing. Pumped in 175 sxs cement with 400# hulls. Max. P.S.I. 1500#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X Elevation: GL

I did [X] / did not [] observe the plugging.

RECEIVED Dennis L. Hamel (agent)
KANSAS CORPORATION COMMISSION Form CP-2/3

INVOICED

DATE 5-15-96

WVL NO. 45600

4-30

MAY 14 1996
5-14-1996

CONSERVATION DIVISION
WICHITA, KS

JUN 27 1996 JUL 17 1996