

4-041731

10-24

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-21,446A

NE NE NE /4 SEC. 26, 12 S, 20 W  
330 feet from N section line  
330 feet from E section line

Operator license# 6127

Lease: King Well # 1

Operator: Taurus Oil Company

County: Ellis 127.47

Address: P.O. Box 981  
Hays, Kansas 67601

Well total depth 3922 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 259 feet  
w/165 sxs.

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00 A.M. Day: 24 Month: October Year 1995

Plugging proposal received from: Jeff Koron

Company: Taurus Oil Company Phone:     

Were: 5 1/2" casing set at 3921' w/150 sxs cement. Perf. at 3816' - 3864'.  
W.L.M. 3860' - T.O.F. at 2100'. Perf. at 1565' cemented with 400 sxs cement and circulated  
at surface. Ordered 200 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 600# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 11:15 A.M., Day: 24, Month: October, Year: 1995

Actual plugging report: R.U. cementers to 5 1/2" casing to squeeze casing at follows:  
25 sxs cement with 200# hulls, followed with 13 sxs gel, followed with 150 sxs cement with  
200# hulls. Max. P.S.I. 700#. S.I.P. 600#. 8 5/8" S.P. R.U. Cementers and squeezed 25 sxs  
cement with 100# hulls. Max. P.S.I. 200#. S.I.P. 100#.

Remarks:     

Condition of casing(in hole): GOOD X BAD      Anyh.plug: YES 1565 NO       
Bottom plug(in place): YES     , CALC X, NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING X. Elevation:      GL

I did[ X ] / did not[      ] observe the plugging

Dennis L. Hamel  
(agent)

Form CP-2/3

**INVOICED**  
DATE 11-1-95  
INV. NO. 43927

RECEIVED  
STATE CORPORATION COMMISSION  
10-30-1995  
OCT 30 1995