



KANSAS CORPORATION COMMISSION 1033122  
OIL & GAS CONSERVATION DIVISION

Form CP-1  
March 2009

This Form must be Typed  
Form must be Signed  
All blanks must be Filled

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

OPERATOR: License #: 30481  
Name: Apollo Energies, Inc.  
Address 1: 10378 N 281 HWY  
Address 2: \_\_\_\_\_  
City: PRATT State: KS Zip: 67124 + 7920  
Contact Person: Kevin Fischer  
Phone: ( 620 ) 672-9001

API No. ~~5~~ - 15-007-02649-00-00  
If pre 1967, supply original completion date: \_\_\_\_\_  
Spot Description: \_\_\_\_\_  
- S2 N2 Sec. 3 Twp. 33 S. R. 11  East  West  
1,980 Feet from  North /  South Line of Section  
2,640 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barber  
Lease Name: WILLIAMS Well #: 1

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: \_\_\_\_\_  
 SWD Permit #: \_\_\_\_\_  ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8.6250 Set at: 278 Cemented with: 250 Sacks  
Production Casing Size: 5.5 Set at: 4590 Cemented with: 125 Sacks

List (ALL) Perforations and Bridge Plug Sets:

Attached

Elevation: 1514 ( G.L. /  K.B.) T.D.: 4590 PBTD: 4555 Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: \_\_\_\_\_  
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

As per KCC Recommendations

Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No

If ACO-1 not filed, explain why:

RECEIVED  
NOV 19 2009  
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Jim Byers  
Address: 10378 N. 281 Hwy City: Pratt State: KS Zip: 67124 + \_\_\_\_\_  
Phone: ( 620 ) 672-9001  
Plugging Contractor License #: 5105 Name: Clarke Corporation  
Address 1: 107 W FOWLER Address 2: \_\_\_\_\_  
City: MEDICINE LODGE State: KS Zip: 67104 + 1534  
Phone: ( 620 ) 886-5665  
Proposed Date of Plugging (if known): 12/02/2009

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Submitted Electronically

Dist 1  
PAG

Form	CP1 - Well Plugging Application
Operator	Apollo Energies, Inc.
Well Name	WILLIAMS 1
Doc ID	1033122

Perforations And Bridge Plug Sets

Perforation Top	Perforation Base	Formation	Bridge Plug Depth
4465	4490		

Form	CP1 - Well Plugging Application
Operator	Apollo Energies, Inc.
Well Name	WILLIAMS 1
Doc ID	1033122

Perforations And Bridge Plug Sets

Perforation Top	Perforation Base	Formation	Bridge Plug Depth
4465	4490		

RECEIVED  
NOV 19 2009  
KCC WICHITA

RECEIVED  
NOV 19 2009  
KCC WICHITA


COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company: HULF OIL CORPORATION  
Farm: C. D. Williams No. 1

SEC. 3 T. 33 R. 11W  
C S/2 N/2  
1980' S. N. L. & 2640'  
E. W. L.  
County Barber KANSAS

Total Depth. 4590'  
Comm. 9-2-56 Comp. 9-20-56  
Shot or Treated.  
Contractor.  
Issued. 11-24-56



CASING:  
8 5/8" @278 w/250 sx cem.  
5 1/2" @4590' w/125 sx cem.

Elevation. 1522' DF

Production. 8,200,000 CFGPD

Figures in locate Bottom of Formations.

clay	40
red rock	280
red bed	690
shale	800
shale & lime	1075
shale	1153
shale & shells	1565
lime	1795
shale & lime	3042
lime	3255
shale	3735
sand & shale	3757
shale	3797
lime	4392
lime & shale	4418
lime	4480
Cherty lime	4493
lime	4502
Cherty lime	4590
Total Depth	

SAND RECORD  
Mississippi Chert  
(4464-4490')

Perf. w/swing jet 4464-90'.  
Acidized w/1000 gals. mud acid.  
sand fraced w/30,000 gals.  
crude 45,000# sand & 1500#  
Adomite.

GEOLOGICAL TOPS	
Heebner	3612
Douglas sand	3737
Brown lime	3799
Lansing-Kansas City	3803
Mississippi chert	4462
Mississippi lime	4513

K. G. S. LIBRARY

RECEIVED  
NOV 19 2009  
KCC WICHITA



Mark Parkinson, Governor  
Thomas E. Wright, Chairman  
Michael C. Moffet, Commissioner  
Joseph F. Harkins, Commissioner

November 19, 2009

Kevin Fischer  
Apollo Energies, Inc.  
10378 N 281 HWY  
PRATT, KS 67124-7920

Re: Plugging Application  
API 15-007-02649-00-00  
WILLIAMS 1  
N/2 Sec.03-33S-11W  
Barber County, Kansas

Dear Kevin Fischer:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after May 18, 2010. The CP-1 filing does not bring the above well into compliance with K.A.R 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,  
Production Department Supervisor

cc: District 1

(620) 225-8888

RECEIVED  
NOV 19 2009  
KCC WICHITA