



KANSAS CORPORATION COMMISSION 1033122  
OIL & GAS CONSERVATION DIVISION

Form CP-1  
March 2009

This Form must be Typed  
Form must be Signed  
All blanks must be Filled

**WELL PLUGGING APPLICATION**

Please TYPE Form and File ONE Copy

OPERATOR: License #: 30481  
Name: Apollo Energies, Inc.  
Address 1: 10378 N 281 HWY  
Address 2: \_\_\_\_\_  
City: PRATT State: KS Zip: 67124 + 7920  
Contact Person: Kevin Fischer  
Phone: (620) 672-9001

API No. ~~15~~- 15-007-02649-00-00  
If pre 1967, supply original completion date: \_\_\_\_\_  
Spot Description: \_\_\_\_\_  
- - S2 N2 Sec. 3 Twp. 33 S. R. 11  East  West  
1,980 Feet from  North /  South Line of Section  
2,640 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barber  
Lease Name: WILLIAMS Well #: 1

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: \_\_\_\_\_  
 SWD Permit #: \_\_\_\_\_  ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8.6250 Set at: 278 Cemented with: 250 Sacks  
Production Casing Size: 5.5 Set at: 4590 Cemented with: 125 Sacks

List (ALL) Perforations and Bridge Plug Sets:

**Attached**

Elevation: 1514 ( G.L. /  K.B.) T.D.: 4590 PBDT: 4555 Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: \_\_\_\_\_  
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

**As per KCC Recommendations**

Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No

If ACO-1 not filed, explain why:

RECEIVED  
NOV 20 2009  
19  
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Jim Byers  
Address: 10378 N. 281 Hwy City: Pratt State: KS Zip: 67124 + \_\_\_\_\_  
Phone: (620) 672-9001  
Plugging Contractor License #: 5105 Name: Clarke Corporation  
Address 1: 107 W FOWLER Address 2: \_\_\_\_\_  
City: MEDICINE LODGE State: KS Zip: 67104 + 1534  
Phone: (620) 886-5665  
Proposed Date of Plugging (if known): 12/02/2009

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Submitted Electronically

Form	CP1 - Well Plugging Application
Operator	Apollo Energies, Inc.
Well Name	WILLIAMS 1
Doc ID	1033122

Perforations And Bridge Plug Sets

Perforation Top	Perforation Base	Formation	Bridge Plug Depth
4465	4490		


COPY

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company- HULF OIL CORPORATION  
Farm- C. D. Williams No. 1

SEC. 3 T. 33 R. 11W  
C S/2 N/2  
1980' S. N. L. & 2640'  
E. W. L.  
County Barber KANSAS

Total Depth. 4590'  
Comm. 9-2-56 Comp. 9-20-56  
Shot or Treated.  
Contractor.  
Issued. 11-24-56



CASINO:  
8 5/8" @278 w/250 sx cem.  
5 1/2" @4590' w/125 sx cem.

Elevation. 1522' DF

Production. 8,200,000 CFGPD

Figures indicate Bottom of Formations.

clay	40
red rock	280
red bed	690
shale	800
shale & lime	1075
shale	1153
shale & shells	1565
lime	1795
shale & lime	3042
lime	3255
shale	3735
sand & shale	3757
shale	3797
lime	4392
lime & shale	4418
lime	4480
Cherty lime	4493
lime	4502
Cherty lime	4590
Total Depth	

K. G. S. LIBRARY

SAND RECORD  
Mississippi Chert  
(4464-4490')

Perf. w/swing jet 4464-90'.  
Acidized w/1000 gals. mud acid.  
sand fraced w/30,000 gals.  
crude 45,000# sand & 1500#  
Adomite.

GEOLOGICAL TOPS	
Heebner	3612
Douglas sand	3737
Brown lime	3799
Lansing-Kansas City	3803
Mississippi chert	4462
Mississippi lime	4513

RECEIVED  
NOV 20 2009  
KCC WICHITA  
KCC #125

