

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
4-10-1967
APR 10 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Rand of Harms Petroleum Co. has this
date requested permission to plug the following described well:

Mr. Rand guarantees payment of the plugging fee.

Operator's full Name: Harms Petroleum Company

Complete Address: P. O. Box 488 Great Bend, Kansas

Lease Name: King Well No. 1

Location: C SW NE Sec. 26 Twp. 12 Rge. 20 (E)(W) X

County Ellis Total Depth 3972 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rand was instructed to plug the well as follows:

Gun pits, circulate Heavy mud, set cementing plug at 550' and displace
20 sc cement thru drill pipe. Heavy mud to 190' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug
1/2 sc hulls and 8 sc cement to base of cellar. Plug rat hole with 2 sc
cement.

Very truly yours,

Ray G. Massey
Conservation Division Agent