



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 11-7-1963  
 NOV 7 1963

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Bob Barnes of Barnes & Sons Pipe Pulling has this

date requested permission to plug the following described well:

Glickmsn Oil Co.,  
 Mr. Barnes guarantees payment of the plugging fee.

Operator's full Name: Glickman Oil Company,

Complete Address: 702 S. St. Francis, Wichita, Kansas.

Lease Name: Horton Well No. 1

Location: SW-SW-SE Sec. 2 Twp. 12 Rge. (E) (W) 21

County Trego Total Depth 4068 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Barnes was instructed to plug the well as follows:

188'--10 3/4" Surface pipe, cement circulated. 4015'--7"  
Production string cemented with 50 Sx.

Sand well back to 4000' and set 5 Sx cement with dump bailer.  
Pull 7" to 600', circulate heavy gel mud and displace 30 Sx.  
cement thru 7". Pull 7" to 180', and displace 30 Sx cement  
thru 7". Pull 7", set rock bridge @ 30' and 10 Sx cement to  
bottom of cellar.

Very truly yours,

*W. L. Nichols*  
 Conservation Division Agent