

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 10-22-1968  
 OCT 22 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Crowe of Garvey Drlg. has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 300 West Douglas Wichita, Ks.

Lease Name: Sutor "L" Well No. 1

Location: SW NE NE Sec. 25 Twp. 10 Rge. 20 (E)(W) X

County: Rooks Total Depth 3769 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:  
Gun pits, circulate heavy mud, set cementing plug at 800' and displace  
70 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Geo F. Messing  
 Conservation Division Agent