

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
12-30-1976
DEC 30 1976

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Curtis of Duke Drlg. has this

date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: Southern States Oil Co.

Complete Address: Box 1365, Great Bend, Kansas

Lease Name: Trarbach Trarbach Well No. 1

Location: NE NE SE Sec. 25 Twp. 10 Rge. (E)(W)20

County: Rooks Total Depth 3775' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Curtis was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 720' thru drill

pipe. Heavy mud to 240' set 20 sk cmt plug thru drill pipe. "eavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent