

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Rooks SEC. 14 TWP. 10S RGE. 20W E/W XXXX
Location as in quarters or footage from lines:
SW SW NE

Lease Owner Nadel and Gussman
Lease Name STITHEM Well No. 19
Office Address 3232 First National Tower-Tulsa, OK 74103
Character of Well (Completed as Oil, Gas or Dry Hole): oil
Date Well Completed April 17, 1956
Application for plugging filed 8/30/82
Plugging commenced 9/16/82
Plugging completed 9/16/82
Reason for abandonment of well or producing formation Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel or Carl Goodrow

Producing formation Arbuckle Depth to top 3747 bottom 3748 T.D. 3750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Arbuckle</u>	<u>oil(depleted)</u>	<u>3747</u>	<u>3748</u>			
				<u>8-5/8"</u>	<u>166'</u>	<u>none</u>
				<u>5-1/2"</u>	<u>3748"</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

200 sacks of 50/50 Poz, 6% gel, 3% calcium chloride, and 3 sacks of hulls
were pumped down the 8-5/8" and 5-1/2" annulus at the same time.
SIP 1000#.

RECEIVED
STATE CORPORATION COMMISSION
10-1-1982
OCT 01 1982
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing Company (Russell, Ks.)

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M.R. Taylor, Mgr. of Prod. (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) M R Taylor
3232 First National Tower-Tulsa, OK 74103
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 19 82

Mildred Carter
Mildred Carter Notary Public.

My Commission expires: 5/11/83



WELL LOG

15-163-02156-00-00

Nadel and Gussman

Stithem No. 19

SW 3W NE 14-10-20W
Rooks County, Kansas

Comm: 4- 8-56
Comp: 4-17-56

Casing: 8-5/8" 166' w/125 sax
5-1/2" 3748' w/

<u>Formations</u>	<u>Depth</u>
Shale and sand	165
Shale and shells	1120
Sand	1330
Shale and red bed	1648
Anhydrite	1680
Shale and shells	1925
Lime and shale	2330
Lime	2440
Lime and shale	2675
Lime	2765
Shale and lime	3285
Lime	3433
Lime and shale	3457
Lime	3750

Geological Tops

Heebner	3426	-1204
Lansing-Kansas C.	3465	-1243
Base Kansas C.	3680	-1458
Conglomerate	3708	-1486
Simpson Shale	3734	-1512
Arbuckle	3747	-1525

RECEIVED
STATE CORPORATION COMMISSION

9-1-1982
SEP 1 1982

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

Elbie G. McNeil, of lawful age, states that the above formations and depths are true according to his best knowledge and belief.

Elbie G. McNeil
Elbie G. McNeil

Subscribed and sworn to before me this 19th day of April, 1956.

Nola Bebb
Nola Bebb, Notary Public

My commission expires Nov. 3, 1956