

15-163-02115-00-00

**TYPE OR PRINT**

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower - Tulsa, OK 74103

PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well input  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6

Is ACO-1 filed? no If not, is well log attached? yes

Producing formation: injection/Arbuckle Depth to top 3754 bottom 3758 T.D. 3781

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	water	3754	58	8-5/8	160'	none
				5-1/2	3777	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from    feet to    feet each set.

Down 7" casing at 1000# max. pressure, 1 sks hulls, 25 sks 60/50 Poz, 20 sks gel, then 115 sks 60/40 Poz;  
Down annulus (10 3/4" csg.) at 300# max. pressure, 1 sks hulls, 200 sks 60/40 Poz  
Witnessed by state rep: Dale Balthazor

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. Inc. License No.                     

Address Box 13 - Russell, KS 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M. R. Taylor (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) MR Taylor  
3232 First National Tower  
(Address) Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 18th day of October, 1985

My Commission expires: 5/11/87

RECEIVED Mildred Carter  
STATE CORPORATION COMMISSION Notary Public

OCT 23 1985  
10-23-1985  
CONSERVATION DIVISION

WELL LOG

NADEL AND GUSSMAN

ELIZA No. 4

SW NE SE 14-10-20W  
Rooks County, Kansas

Comm: 6- 2-52  
Comp: 6-12-52

Casing: 10-3/4" 160' w/100 sax  
7" 3777' w/100 sax

<u>Formations</u>	<u>Depth</u>
Clay, sand	40
Shale and shells	590
Shale, shells and sand	1115
Sand, red bed, shale and shells	1570
Shale, shells and red bed	1648
Anhydrite	1687
Shale and lime	1900
Shale, shells	2130
Broken lime and shale	2395
Lime and shale	3484
Lime	3532
Lime and shale	3622
Lime	3671
Lime and Conglomerate	3731
Conglomerate	3757
Arbuckle	3758

Geological Tops

Heebner Shale	3429
Lansing-K.C.	3469
B. Kansas City	3682
Conglomerate	3709
Simpson	3750
Arbuckle	3755

STATE OF KANSAS }  
COUNTY OF SEDGWICK } SS:

George Reed, of lawful age, deposes and states that the above formations and depths are correct as shown by the daily drilling log of the Eliza Well No. 4 in the SW NE SE 14-10-20W, Rooks County, Kansas.

George Reed

Subscribed and sworn to before me this 17th day of June, 1952,

Notary Public

My commission expires Nov. 3, 1952

RECORDED  
STATE CORPORATION COMMISSION

8-8  
AUG 8

CONSERVATION DIVISION  
Wichita, Kan.