

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME ELIZA

WELL NUMBER #5

SPOT LOCATION C EL NW SE

SEC. 14 TWP. 10 RGE. 20 (N) or (W)

COUNTY Rooks

Date Well Completed 10-16-54

Plugging Commenced 5-10-84

Plugging Completed 5-10-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower - Tulsa, OK 74103

PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6 - Hays, Ks.

Is ACO-1 filed? Not required If not, is well log attached? Yes

Producing formation Arbuckle Depth to top 3749 bottom 3751 T.O. 3751

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil (depleted)	3749	51	8-5/8"	199'	None
				5-1/2"	3750'	"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped 250 sax 50/50 Poz, 4% Gel & 3% Ca Cl down 5-1/2" - 700# Max Press
Pumped 150 sax 50/50 Poz, 4% Gel & 3% Ca Cl down annulus between 8-5/8" & 5-1/2" 500#
Max. Press.

Witnessed by Dennis Hamel - State Plugger
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. N/A
Address Box 31 - Russell, Kansas 67665

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

M. R. Taylor (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) MR Taylor
3232 First National Tower
(Address) Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 18 day of May, 1984

Mildred Carter
Notary Public
Mildred Carter

My Commission expires: May 11, 1987

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1984
5-21-1984
CONSERVATION DIVISION
Wichita, Kansas



Nadel and Gussman

Eliza No. 5

c EL NW SE 14-10-20W
Rooks County, Kansas

Comm: 10-7-54
Compt: 10-16-54

Casing: 8-5/8" 199' w/125 sax
5-1/2" 3750' w/150 sax

Sand and shale	200
Shale	1045
Shale, sand and red bed	1640
Red bed	1652
Anhydrite	1690
Shale and shells	2205
Shale and broken lime	2305
Shale and lime	3175
Line	3255
Line and shale	3342
Line	3595
Line and shale	3703
Chert	3719
Shale	3749
Line	3751

Geological Tops

Heebner Shale	3424
Lansing-Kansas City	3462
Base Kansas City	3677
Conglomerate	3703
Simpson Shale	3744
Arbuckle	3749

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

L. C. Hay, of lawful age, deposes and states that the above depths and formations are correct as shown by the daily drilling log of the Eliza No. 5 Well in the Center of the East Line of the NW SE of 14-10-20W, Rooks County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 19th day of October, 1954.

W. A. Bass
Notary Public

My commission expires Nov. 3, 1956

RECEIVED
STATE CORPORATION COMMISSION
2-15-1964
FEB 15 1964
CONSERVATION DIVISION
Wichita, Kansas