

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY \_\_\_\_\_ Rooks \_\_\_\_\_ SEC. 14 TWP. 10S RGE. 20W ~~E/W~~  
Location as in quarters or footage from lines:  
SE NE SE


Locate Well  
correctly on above  
Section Platt.

Lease Owner Nadel and Gussman  
Lease Name ELIZA Well No. 6  
Office Address 3232 First National Tower-Tulsa, OK 74103  
Character of Well (Completed as Oil, Gas or Dry Hole): oil  
Date Well Completed Dec. 29, 1955  
Application for plugging filed 8/30/82  
Plugging commenced 9/16/82  
Plugging completed 9/16/82  
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel & Carl Goodrow  
Producing formation Arbuckle Depth to top 3763 bottom 3767 T.D. 3767  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Arbuckle	oil(depleted)	3763	3767			
				8-5/8"	145'	none
				5-1/2"	3764'	none

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.  
250 sacks of 50/50 Poz, 6% gel, 3% calcium chloride, and 3 sacks of hulls were  
pumped down the 8-5/8" and 5-1/2" annulus at the same time. SIP 900#

RECEIVED  
STATE CORPORATION COMMISSION  
10-1-1982  
OCT 01 1982  
CONSERVATION DIVISION  
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Allied Cementing Company (Russell, Ks.)

STATE OF Oklahoma COUNTY OF Tulsa, ss.  
M. R. Taylor, Mgr. of Prod. (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) M R Taylor  
3232 First National Tower-Tulsa, OK 74103  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 1982

Mildred Carter  
Mildred Carter Notary Public.

My Commission expires: 5/11/83



WELL LOG

NADEL AND GUSSMAN

ELIZA No. 6

SE NE SE 14-10-20W  
Rooks County, Kansas

Comm: 12-17-55  
Comp: 12-29-55

Casing: 8-5/8" 145' w/135 sax  
5-1/2" 3764' w/125 sax

Formations

Depth

Sand	50
Shale	145
Shale and shells	810
Sand	870
Shale and shells	1220
Sand	1370
Shale, shells and red bed	1643
Anhydrite	1680
Shale and shells	2380
Lime and shale	2635
Shale	2810
Shale and lime	3285
Lime	3415
Lime and shale	3465
Lime	3695
Lime and chert	3760
Shale	3763
Lime	3767

Geological Tops

Heebner	3434
Toronto	3453
Lansing-K.C.	3476
Base Kansas City	3684
Conglomerate	3712
Simpson	3757
Arbuckle	3763

RECEIVED  
STATE CORPORATION COMMISSION  
9-1-1982  
SFP 1 1982  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) SS:  
COUNTY OF SEDGWICK )

L. C. Hay, of lawful age, states that the above formations and depths are correct as shown by the daily drilling report of the Eliza No. 6 Well in the SE NE SE 14-10-20W, Rooks County, Kansas.

L. C. Hay  
L. C. Hay

Subscribed and sworn to before me this 30th day of December, 1955.

Paula Berry  
Notary Public

My commission expires Nov. 3, 1956