

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A
LEASE NAME ELIZA
WELL NUMBER #8
SPOT LOCATION NE NE SE
SEC. 14 TWP. 10 RGE. 20 (●) or (W)
COUNTY Rooks
Date Well Completed 5-21-86
Plugging Commenced 5-10-84
Plugging Completed 5-10-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman
ADDRESS 3232 First National Tower - Tulsa, OK 74103
PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6 - Hays, Kansas

Is ACO-1 filed? Not required If not, is well log attached? Yes

Producing formation Arbuckle Depth to top 3719 bottom 3721 T.O. 3721

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil (depleted)	3719	21	10-3/4"	176'	None
				5-1/2"	3720'	"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped 215 sax 50/50 Poz, 4% Gel, 3% Ca Cl down 5-1/2" - 800# Max Pressure
Pumped 100 sax 50/50 Poz, 4% Gel, 3% Ca Cl down annulus between 10-3/4" & 5-1/2"
600# Max. Pressure.

Witnessed by Dennis Hamel - State Plugger

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. N/A
Address Box 31 - Russell, KS 67665

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

M. R. Taylor (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M R Taylor
(Address) 3232 First National Tower Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 18th day of May, 19 84

Mildred Carter
Notary Public
Mildred Carter

My Commission Expires: May 11, 1987

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1984
5-21-1984
CONSERVATION DIVISION
Wichita, Kansas



WELL LOG

Nadel and Gussman

ELIZA No. 8

NE NE SE 14-10-20W
Rooks County, Kansas

Comm: 5-11-56
Comp: 5-21-56

Casing: 10-3/4" 176' w/135 sax
5-1/2" 3720' w/150 sax

Formations

Depth

Sand and shale	176
Shale and shells	1030
Sand	1300
Shale	1325
Shale and shells	1595
Anhydrite	1615
Shale, shells and salt	1930
Shale and shells	2150
Lime and shale	2183
Lime	2560
Shale and lime	3030
Lime	3165
Lime and shale	3310
Lime	3370
Lime and shale	3400
Shale	3414
Lime	3721

Geological Tops

Heebner Shale	3394
Lansing-Kansas City	3431
Base Kansas City	3644
Conglomerate	3672
Simpson Shale	3714
Arbuckle	3719

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

E. G. McNeil, of lawful age, deposes and states that the above formations and depths are correct to his best knowledge and belief.

E. G. McNeil
E. G. McNeil

Subscribed and sworn to before me this 24th day of May, 1956.

Nola Babb
Nola Babb, Notary Public

My commission expires Nov. 3, 1956.

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1984
CONSERVATION DIVISION
Wichita, Kansas