

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME ELIZA

WELL NUMBER #7

SPOT LOCATION SE NW SE

SEC. 14 TWP. 10 RGE. 20 (■) or (W)

COUNTY Rooks

Date Well Completed 4-29-56

Plugging Commenced 5-10-84

Plugging Completed 5-10-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower - Tulsa, OK 74103

PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #6 - Hays, Ks.

Is ACO-1 filled? not required if not, is well log attached? Yes

Producing formation Arbuckle Dolomite Depth to top 3750 bottom 3753 T.D. 3753

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle Dolomite	Oil (depleted)	3750	53			
				8-5/8"	165'	None
				5-1/2"	3751'	"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped 200 sax 50/50 Poz, 4% Gel & 3% Ca Cl down 5-1/2" - 700# Max. Pressure.
Pumped 150 " 50/50 Poz, 4% Gel & 3% Ca Cl down annulus between 8-5/8" and 5-1/2"
500# Max. Pressure.

Witnessed by Dennis Hamel - State Plugger

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. N/A

Address Box 31 - Russell, Ks. 67665

RECEIVED
STATE CORPORATION COMMISSION

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

M. R. Taylor (employee of operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M R Taylor
3232 First National Tower
(Address) Tulsa, OK 74103

MAY 21 1984
5-21-1984
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 18th day of May, 1984

Mildred Carter
Notary Public
Mildred Carter

My Commission expires: May 11, 1987

WELL LOG

Nadel and Gussman

ELIZA No. 7

SE NW SE 14-10-20W
Rooks County, Kans.

Comm: 4-20-56
Comp: 4-29-56

Casing: 8-5/8" 165' w/125 sax
5-1/2" 3751' w/150 sax

Formations

Depth

Sand and shale	165
Shale and shells	1180
Sand	1380
Red bed and shale	1565
Shale and shells	1647
Anhydrite	1690
Shale and shells	2150
Shale and lime	2195
Lime	2425
Lime and shale	2620
Shale	2875
Lime and shale	3118
Lime	3753

Geological Tops

Anhydrite	1647
Heebner Shale	3423
Lansing-Kansas City	3461
Base Kansas City	3671
Base Penn. Cong.	3702
Reworked Simpson Sh.	3725
Simpson Shale	3740
Arbuckle Dolomite	3750 Corr.

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

Elbie G. McNeil, of lawful age, states that the above formations and depths are correct to his best belief.

Elbie G. McNeil

Elbie G. McNeil

Subscribed and sworn to before me this 11th day of May, 1956

Nola Babb

Nola Babb, Notary Public

My commission expires Nov. 3, 1956

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1956
CONSERVATION DIVISION
Wichita, Kansas