

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Rooks County, Sec. 14 Twp. 10 Rge. 20 (E) (W)
Location as "NE/CNW/SW" or footage from lines. CE/2 SW/4 SE/4
Lease Owner I. O. Miller
Lease Name Sutor Well No. 5
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 5/2/68 19____
Plugging completed 5/3/68 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3780 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	243'	none
				5 1/2"	3779'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 2300' and ran sand and 5 sacks of cement.
Loaded hole with water, shot pipe at 327' and 238', bailed hole to 230', set rock bridge and ran 15 sacks of cement. Mudded to 40', set rock bridge and ran 5 sacks of cement.

PLUGGING COMPLETE.


RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first and sworn deponent, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct. So help me God.



(Signature) Noel Knight
CHASE, KANSAS
(Address)

Subscribed and sworn to before me this 6th day of May, 1968
Margaret Melcher
Notary Public.

My commission expires February 15, 1971

Sutor # 5 - C E/2 SW/4 SE/4 Sec. 14-10-20 Rooks County, Kansas
 Company - I. C. Miller
 Contractor - Virginia Drlg. Co Inc.
 Commenced - Nov. 15, 1954
 Completed - rotary hole - Nov. 26, 1954
 Elevation - 2236 KB
 Total Depth - 3780

8 5/8" set at 243 ft.
 5 1/2" set at 3779 ft. w/125 SX con.
 TV tool set at 1698 w/ 650 AX.

FORMATION	DEPTH
Shale	0- 40
Sand	40- 110
Shale	110- 243
Shale-shells-sand	243- 890
Shale-sand	890-1400
Shale-shells	1400-1580
Shale	1580-1669
Anhydrite	1669-1702
Shale	1702-1835
Shale-shells	1835-2380
Broken lime	2380-2510
Lime	2510-2620
Shale-shells	2620-2965
Shale-lime	2965-3345
Lime	3345-3400
Lime-shale	3400-3495
Lime	3495-3720
Lime-shale	3720-3741
Conglomerate	3741-3759
Simpson shale	3759-3775
Lime	3775-3780 TL

- TOPS:
- 3245 - Topeka
 - 3452 - Heebner
 - 3473 - Toronto
 - 3491 - Lansing KC
 - 3719 - Base K C
 - 3741 - Conglomerate
 - 3759 - Simpson
 - 3778 - Arbuckle

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 10 1968
 CONSERVATION DIVISION
 Wichita, Kansas

S. A. Murphy
 S. A. Murphy

Subscribed and sworn to, before me, a Notary Public,
 this 2nd day of December 1954.

Marla Hawkins
 Notary Public

My commission expires: Febr. 5, 1957.