

15-163-02159-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME Stithem

WELL NUMBER 22

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 14 TWP. 10 SRGE. 20 (X) or (W)

COUNTY Rooks

Date Well Completed 6-30-56

Plugging Commenced 11-12-92

Plugging Completed 11-12-92

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3200 First National Tower, Tulsa, OK 74103

PHONE#(918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-6-92 (date)

by Dennis L. Hamel (KCC District Agent's Name).

Is ACO-1 filed?            If not, is well log attached? yes

Producing Formation Lansing KC Depth to Top 3652 Bottom 3679 T.D. 3770

P.B.T.D. 3731

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing KC	Oil & water	3486	3702	8-5/8	167'	
Arbuckle	Oil & water	3768	3770	5-1/2	3769'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from        feet to        feet each set.  
Ran tubing to 3000' and spotted 75 sks cement on bottom. Pulled tubing and cemented down 5-1/2 csg @ 500# max. pressure w/300 lbs hulls and 200 sks cement. Shut in @ 300#. Pumped down annulus (8-5/8 csg) @ 500# max. w/100# hulls and 75 sks cement. Shut in @ 400#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. n/a

Address P.O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M.R. Taylor, Manager of Production (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M.R. Taylor

(Address) 3200 First National Tower  
Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 19 92

Kathy Sparron NOV 30 1992  
Notary Public 11-30-1992

My Commission Expires: 8-1-95

RECEIVED  
CORPORATION COMMISSION  
Form CP-4  
Revised 05-88

WELL LOG

Nadel and Gussman

Stithem No. 22

NE NE SW 14-10-20W  
Rooks County, Kans.

Comm: 6-20-56

Comp: 6-30-56

Casing: 8-5/8" 167' w/135 sax  
5-1/2" 3769' w/150 sax

Formations

Depth

Surface  
Shale and shells  
Anhydrite  
Shale and shells  
Lime and shale  
Lime

167  
1666  
1705  
2220  
3391  
3770

GEOLOGICAL TOPS

Heebner 3450'  
Toronto 3471'  
Lans.-K.C. 3486'  
Base K.C. 3702'  
Conglomerate 3730'  
Arbuckle 3768'

STATE OF KANSAS )  
COUNTY OF SEDGWICK } SS:

The above formations and depths are correct to my best knowledge.

L. C. Hay  
L. C. Hay

Subscribed and sworn to before me this 2nd day of July, 1956.

Nola Babb  
Nola Babb, Notary Public  
RECEIVED  
STATE CORPORATION COMMISSION

My commission expires Nov. 3, 1956

OCT 26 1956  
10-26-1992  
CONSERVATION DIVISION  
Wichita, Kansas

15-163-02159-00-00

TELEPHONE:  
AREA CODE 913 483-2627

**ALLIED CEMENTING COMPANY, INC.**

P. O. BOX 31  
RUSSELL, KANSAS 67665

TO: Nadel & Gussman  
P. O. Box 14  
Great Bend, KS 67530

INVOICE NO. 62909  
PURCHASE ORDER NO. \_\_\_\_\_  
LEASE NAME Stithem #22  
DATE Nov. 12, 1992

SERVICE AND MATERIALS AS FOLLOWS:

Common 210 sks @\$5.50	\$1,155.00	
Pozmix 140 sks @\$2.50	350.00	
Gel 24 sks @\$6.75	162.00	
Hulls 4 sks @\$15.00	<u>60.00</u>	\$1,727.00
Handling 350 sks @\$1.00	350.00	
Mileage (15) @\$.04¢ per sk per mi	210.00	
Plug	<u>150.00</u>	710.00
	Sales tax	<u>131.60</u>
	Total	\$2,568.60

Thank you!

All Prices Are Net, Payable 30 Days Following Date of Invoice. 1½% Charged Thereafter.

RECEIVED  
NOV 30 1992  
OPERATION COMMISSION

Phone 913-483-2627, Russell, Kansas

Phone Plainville 913-434-2812

Phone 316-793-5861, Great Bend, Kansas

Phone Ness City 913-798-3843

old

# ALLIED CEMENTING CO., INC.

2157

Home Office P. O. Box 31

Russell, Kansas 67665

Date	11-12-92	Sec.	14	Twp.	10 <sup>s</sup>	Range	20 <sup>w</sup>	Called Out	5:30 A.M.	On Location	11:45 A.M.	Job Start	Noon	Finish	2:45 P.M.
Lease	Stithem	Well No.	22	Location	Zunich 3W 35 1/2 W 1/2 S 1/2 W	County	Rooks	State	Ks.						

Contractor	C & W Well Service		
Type Job	Plug to Abandon		
Hole Size	7 7/8"	T.D.	3700'
Csg.	5 1/2"	Depth	3769'
Tbg. Size	2 1/2"	Depth	
Surface Drill Pipe	8 7/8"	Depth	167'
Tool		Depth	
Cement Left in Csg.		Shoe Joint	
Press Max.		Minimum	
Meas Line		Displace	
Perf.			

Owner	Same
To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.	
Charge To	Nadel & Gussman
Street	P.O. Box 14
City	Great Bend, State Ks. 67530
The above was done to satisfaction and supervision of owner agent or contractor.	

Purchase Order No.	
X	Frank Heff
	CEMENT

**EQUIPMENT**

Pumptrk	No. 191	Cementer	Gary H.
		Helper	Bill Mc
Pumptrk	No.	Cementer	
		Helper	
Bulktrk	#218	Driver	Mark D.
Bulktrk	#212	Driver	Joe S.

Amount Ordered	350 sks 60/40 poz 10 2 gal	
Consisting of	4 sks hulls	
Common	210 sks @ 5.50/sk	\$1155.00
Poz. Mix	140 sks @ 2.50/sk	350.00
Gel.	24 sks @ 6.75/sk (Used 30 sks)	162.00
Chloride		
Quickset		
Hulls	4 sks @ 15.00/sk	60.00

<b>DEPTH of Job</b>	
Reference #9	Pumptruck-plug 2 <sup>nd</sup> well #150.00
#13	mileage n/c
Sub Total	#150.00
Tax	
Total	

Handling	@ 1.00/sk. (350 sks)	350.00
Mileage	@ 0.44/sk./mi. (15 mi)	210.00
Sub Total		#2287.00
Total		
Floating Equipment	Thanks	

Remarks: Ran sky to 3000' and mixed 75 sks cement. Pulled sky down 5 1/2" csg., at 500# max pressure, mixed 300# hulls with 200 sks cement, and shut in at 300' Down annulus (8 7/8" csg.), at 500# max pressure, mixed 100# hulls with 75 sks cement, and shut in at 400#

RECEIVED  
STATE COMMISSION  
11-30-1992  
NOV 30 1992