

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-163-02148-00-00

RECEIVED  
 7-7-2003  
 JUL 07 2003

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

API NUMBER NA

LEASE NAME Stithem

WELL NUMBER 10

3630 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 14 TWP. 10 RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 9/20/51

Plugging Commenced 6/19/03

Plugging Completed 6/19/03

KCC WICHITA

LEASE OPERATOR Nadel and Gussman, L.L.C.

ADDRESS 15 E. 5th St., Suite 3200, Tulsa, OK 74103

PHONE# (918) 583-3333 OPERATORS LICENSE NO. 32638

Character of Well \_\_\_\_\_

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/16/03 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation KC & Arbuckle Depth to Top 3652 Bottom 3782 T.D. 3784

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
KC	Depleted oil	.0	158	8-5/8	158	None - cemented to surface
Arbuckle	Depleted oil	0	3781	5-1/2	3781	None - cemented w/125 sks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. Perforated well @ 975' (2 holes) and 1750' (2 holes). Pumped down 5-1/2 w/25 sks cement w/200# hulls and 18 sks gel followed by 200 sks cement w/200# hulls @ 1000# max psi. SI @ 400 psi. Pumped down backside w/25 sks cement and 100# hulls @ 600 psi. Max shut in @ 200 psi. Used total of 250 sks 60/40 poz w/10% gel.

Name of Plugging Contractor Allied Cementing License No. N/A

Address P.O. Box 31, Russell, KS 67605

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman, L.L.C.

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M.R. Taylor, Manager of Production (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M R Taylor

(Address) 3200 First Place Tower, Tulsa, OK 74103



SWORN TO before me this 3rd day of July, 19 2003

Kathy Garrow  
 Notary Public

7-7-2003  
JUL 07 2003

KCC WICHITA

WELL LOG

NADEL AND GUSSMAN

STITHEM No. 10

NW SE NW 14-10-20W  
Rocks County, Kansas

Comm. 9-12-51  
Comp. 9-20-51

Casing: 8-5/8" 158'  
5-1/2" 3787' w/125 sax  
3781'

Formations	Depth
Surface	159
Shale, shells and sand	1670
Anhydrite	1710
Shale, shells	2040
Broken Lime	2280
Broken lime and shale	2374
Lime and shale	2480
Lime	2588
Lime and shale	3503
Lime	3764
Conglomerate	3780
Arbuckle	3782

Geological Tops

Heebner	3461
Toronto Lime	3487
Lansing-Kansas City	3499
Base Kansas City	3714
Conglomerate	3733
Simpson Shale	3776
Arbuckle	3780
R.T.D.	3782

STATE OF KANSAS

COUNTY OF SEDGWICK

} SS:

George A. Reed, of lawful age, deposes and states that the above formations and depths are true and correct as shown by the daily drilling log of the Stithem No. 10 in the NW SE NW 14-10-20W, Rocks County, Kansas.

Subscribed and sworn to before me this 25th day of September, 1951.

My commission expires 11-3-52

*[Signature]*  
Notary Public