

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-02131-00-00

API NUMBER N/A

LEASE NAME Stithem

WELL NUMBER 2

4950 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 14 TWP. 10S RGE. 20 (E) or (W)

COUNTY Rooks

Date Well Completed 3/24/51

Plugging Commenced 11/12/92

Plugging Completed 11/12/92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3200 First National Tower, Tulsa, OK 74103

PHONE#(918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-6-92 (date)

by Dennis L. Hamel (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? yes

Producing Formation Arbuckle Depth to Top 3784 Bottom 3786 T.D. 3789

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing KC	Oil & water	3449	3712	8-5/8	160'	
Arbuckle	Oil & water	3784	3786	5-1/2	3780'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Ran 3018' tubing and spotted 75 sks cement on bottom. Pulled tubing to 2050' and circulated 75 sks cement to surface. Pulled tubing and pumped down 5-1/2 casing @ 800# max. pressure. Pumped in 300# hulls w/100 sks cement. Shut in @ 400#. Pumped down annulus (8-5/8 csg) @ 300# max. w/100# hulls and 50 sks cement. Shut in @ 100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. n/a

Address P.O. Box 31, Russell, Kansas 67665

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman

NOV 30 1992

STATE OF Oklahoma COUNTY OF Tulsa, ss.

11-30-1992

M.R. Taylor, Manager of Production (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M.R. Taylor

(Address) 3200 First National Tower
Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 19 92

Rachy Carver
Notary Public

My Commission Expires: 8-1-95

WELL LOG

NADEL AND GUSSMAN

STITHEM No. 2

NW NE NW 14-10-20W
Rooks County, Kansas

Comm. 3-15-51
Comp. 3-24-51

Casing: 8-5/8" 160' W/110 Sax
5-1/2" 3780' W/125 Sax

Formation	Depth
Surface soil, sand, shale	163
Shale, sand, shells and Red Bed	1030
Shale, sand and shells	1130
Sand	1390
Shale and shells	1470
Shale, shells & red bed	1675
Anhydrite	1720
Red bed and shale	1860
Shale and shells	2355
Broken lime	2525
Broken Lime, shale	2615
Lime and shale	3502
Lime	3723
Lime, shale and chert	3758
Conglomerate	3774
Shale	3784
Arbuckle	3786

GEOLOGICAL TOPS

Heebner Shale	3460
Toronto Lime	3479
Lansing-Kansas City	3499
B. Kansas City	3712
Conglomerate	3745
Simpson shale	3774
Arbuckle	3784
T.D.	3786

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

L. C. Hay of lawful age deposes and states that the above formations and depths are true and correct as taken from the daily drilling log of the Stithem No. 2 well in the NW NE NW 14-10-20W, Rooks County, Kansas.

Subscribed and sworn to before me this 28th day of March, 1951,

My commission expires Nov. 3, 1952

L. C. Hay

[Signature]

Notary Public

RECEIVED
NOV 30 1992
11-30-1992

Phone 913-483-2627, Russell, Kansas

Phone Plainville 913-434-2812

Phone 316-793-5861, Great Bend, Kansas

Phone Ness City 913-798-3843

old

ALLIED CEMENTING CO., INC.

2156

Home Office P. O. Box 31

Russell, Kansas 67665

Date	11-12-92	Sec.	14	Twp.	10 ^s	Range	20 ^w	Called Out	5:30 A.M.	On Location	8:00 A.M.	Job Start	8:30 A.M.	Finish	11:30 A.M.
Lease	Stithem	Well No.	2	Location				Zurich 3W351 ³ / ₄ W ³ / ₈ S	County	Rooks	State	Ks.			

Contractor	C & L Well Service		
Type Job	Plug to Abandon		
Hole Size	7 ⁷ / ₈ "	T.D.	3786'
Csg.	5 ¹ / ₂ "	Depth	3780'
Tbg. Size	2 ¹ / ₂ "	Depth	
Surface Drill Pipe	8 ⁷ / ₈ "	Depth	160'
Tool		Depth	
Cement Left in Csg.		Shoe Joint	
Press Max.		Minimum	
Meas Line		Displace	
Perf.			

Owner	Same
To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.	
Charge To	Nadel & Gussman
Street	P.O. Box 14
City	Great Bend, State Ks. 67530
The above was done to satisfaction and supervision of owner agent or contractor.	
Purchase Order No.	
X <i>Frank Neff</i>	

EQUIPMENT

No.	Cementer	Gary H. Bill Mc.
Pumptrk #191	Helper	
No.	Cementer	
Pumptrk	Helper	
	Driver	Joe S.
Bulktrk #212	Driver	

CEMENT	
Amount Ordered	300 sks 69/40 002 10% gel
Consisting of	4 sks hulls
Common	180 sks @ 5.50/sk. \$990.00
Poz. Mix	120 sks @ 2.50/sk. 300.00
Gel. Chloride	21 sks @ 6.75/sk. (used 26 sks) 141.75
Quickset	
Hulls	4 sks @ 15.00/sk. 60.00
Sales Tax	
Handling	@ 1.00/sk. (300 sks) 300.00
Mileage	@ 0.4 \$/sk./mi. (15 mi.) 180.00
Sub Total	\$1971.75
Total	

DEPTH of Job

Reference:	#9 Pumptruck - plug well	360.00
	#13 mileage @ 2.00/mi	30.00
Sub Total		\$390.00
Tax		
Total		

Floating Equipment	Thanks
RECEIVED COMMISSION 11-30-1992 NOV 30 1992	

Remarks: Ran to 3018' and mixed 75 sks cement.
 Pulled to 2050' and circulated cement back to surface with 75 sks.
 Pulled to down 5¹/₂" csg. at 800# max pressure, mixed 300# hulls with 100 sks cement, and shut in at 400#. Down annulus (8⁷/₈" csg.) at 300# max. pressure, mixed 100# hulls with 50 sks cement, and shut in at 100#.

15-163-02131-00-00

TELEPHONE:
AREA CODE 913 483-2627

ALLIED CEMENTING COMPANY, INC.
P. O. BOX 31
RUSSELL, KANSAS 67665

TO: Nadel & Gussman
P. O. Box 14
Great Bend, KS 67530

INVOICE NO. 62910
PURCHASE ORDER NO. _____
LEASE NAME Stithem #2
DATE Nov. 12, 1992

SERVICE AND MATERIALS AS FOLLOWS:

Common 180 sks @\$5.50	\$990.00	
Pozmix 120 sks @\$2.50	300.00	
Gel 21 sks @\$6.75	141.75	
Hulls 4 sks @\$15.00	<u>60.00</u>	\$1,491.75
Handling 300 sks @\$1.00	300.00	
Mileage (15) @\$.04¢ per sk per mi	180.00	
Plug	360.00	
Mi @\$2.00 pmp trk chg	<u>30.00</u>	870.00
	Sales tax	<u>127.53</u>
	Total	\$2,489.28

Thank you!

All Prices Are Net, Payable 30 Days Following Date of Invoice. 1½% Charged Thereafter.

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1992
11-30-1992
KANSAS