

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-02160-00-00

API NUMBER N/A

LEASE NAME STITHEM

WELL NUMBER 23

SPOT LOCATION NE SE NE

SEC. 14 TWP. 10S RGE. 20 (E) (W)

COUNTY Rooks

Date Well Completed 1/7/57

Plugging Commenced 10/15/85

Plugging Completed 10/15/85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower - Tulsa, OK 74103

PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6

Is ACO-1 filed? N/A If not, is well log attached? yes

Producing formation Arbuckle Depth to top 3732 bottom 3738 T.D. 3738

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	oil (depleted)	3732	38	8-5/8	205'	none
				5-1/2	3733'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Down 5 1/2", 2 sks hulls, 25 sks 60/40 Poz, 10 sks gel, then 150 sks 60/40 Poz 400#psi Max 8-5/8" surface backside, 150 sks 60/40 Poz, with 2 sks hulls 300#psi Max

Witnessed by state rep: Gil Balthazor

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. Inc. License No. _____

Address Box 31 - Russell, KS 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M. R. Taylor (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. R. Taylor

(Address) 3232 First National Tower Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 85

STATE CORPORATION COMMISSION

Mildred Carter
Notary Public

My Commission expires: 5/11/87

RECEIVED
OCT 23 1985
10-23-1985
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Nadel and Gussman

STITHEN No. 23

NE SE NE 14-10-20W
Rooks County, Kansas

Conn: 12-28-56

Comp: 1-7-57

Casing: 8-5/8" 205' w/135 sax
5-1/2" 3733' w/150 sax

Formations

Depth

GEOLOGICAL TOPS

Surface	205
Shale	870
Sand and shale	1330
Shale and shells	1620
Anhydrite	1665
Shale	1940
Lime and shale	3440
Lime	3640
Lime-Conglomerate	3720
Conglomerate and Arbuckle	3735
RTD	3735

Heebner	3406
Toronto	3427
Lansing	3444
Base Kansas City	3656
Conglomerate	3680
Simpson Shale	3722
Arbuckle	3732

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

L. C. Hay, of lawful age, states that the above formations and depths are correct to his best knowledge and belief.

L. C. Hay

Subscribed and sworn to before me this 10th day of January, 1957.

Paula B...
Notary Public

My commission expires Nov. 3, 1960

RECEIVED
STATE COOPERATION COMMISSION

8-8
AUG 8

CONSERVATION DIVISION
Wichita, Kansas