

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

K.A.R.-82-3-117

15-163-02140-00-00

API NUMBER N/A

LEASE NAME STITHEM

WELL NUMBER 8

SPOT LOCATION SE NW NE

SEC. 14 TWP. 10S RGE. 20 ~~XXXXX~~ (W)

COUNTY Rooks

Date Well Completed 7/25/51

Plugging Commenced 7/21/87

Plugging Completed 7/21/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower
Tulsa, OK 74103

PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #4 Hays, KS

Is ACO-1 filed? N/A If not, is well log attached? yes

Producing formation Arbuckle Depth to top 3764 bottom 3765 T.D. 3769

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	125	none
				5-1/2	3764	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Filled 5-1/2" casing with 150 sacks ATL cement, 1 sack hulls, PSI 500# Max.

Put 100 sacks ATL cement, 2 sacks hulls down surface backside, PSI 300# Max

Witnessed by KCC Rep: Dennis Hamel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No.

Address P.O. Box 31, Russell, KS 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M. R. Taylor

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

AUG 3 1987
8-3-1987

CONSERVATION DIVISION
WICHITA, KANSAS

(Signature) M. R. Taylor

(Address) 3232 First National Tower

Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 31 day of July, 19 87

Mildred Carter
Notary Public

My Commission expires: 5/11/91

WELL LOG

NADEL AND GUSSMAN

Stithem No. 8

SE NW NE 14-10-20W
Rooks County, Kansas

Comm: 7-18-51
Comp. 7-25-51

Casing: 8-5/8" @ 125'
5-1/2" @ 3764' w/100 Sax

Formation	Depth
Surface, shale and sand	125
Shale and sand	750
Shale and shells	1135
Sand	1390
Shale, red bed and shells	1570
Shale and red bed	1669
Anhydrite	1714
Shale, red bed and shells	2015
Shale and broken lime	2270
Lime	2382
Shale	2445
Broken Lime	2545
Lime and Florence Flint	2603
Shale and shells	2880
Lime and shale	3496
Lime	3682
Lime and shale	3775

Geological Tops

Heebner Shale	3440
Toronto Lime	3465
Lansing-Kansas City	3478
Conglomerate	3719
Simpson Shale	3756
Arbuckle	3763-3765

SLM Correction 3775=3765'

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

L. C. Hay, of lawful age, being duly sworn states that the above formations and depths are true and correct as taken from the daily drilling log of the Stithem No. 8 Well in the SE NW NE 14-10-20W, Rooks County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 1st day of August, 1951

Wola B. Bandy
Notary Public

My commission expires Nov. 3, 1952

8-3-1987
AUG 3 1987