

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-02161-00-00

API NUMBER N/A

LEASE NAME STITHEM

WELL NUMBER 24

SPOT LOCATION SE NE NE

SEC. 14 TWP. 10S RGE. 20 (W)

COUNTY Rooks

Date Well Completed 1/18/57

Plugging Commenced 10/15/85

Plugging Completed 10/15/85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower - Tulsa, OK 74103

PHONE # 918-583-3333 OPERATORS LICENSE NO. 5337

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6

Is ACO-1 filed? N/A If not, is well log attached? yes

Producing formation Arbuckle Depth to top 3735 bottom 3738 T.D. 3738

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	oil (depleted)	3735	38	8-5/8	192	none
				5-1/2	3236	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Down 5 1/2", 1 sk hulls, 25 sks 60/40 Poz, 10 sks gel, then 150 sks 60/40 poz 400# psi Max
8-5/8" surface backside, 150 sks 60/40 Poz with 3 sks hulls 300# psi Max
Witnessed by state rep: Gil Balthazor

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. Inc. License No. _____

Address Box 13 - Russell, KS 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M. R. Taylor (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) me Taylor
3232 First National Tower
(Address) Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 84

STATE CORPORATION COMMISSION

10-23-1985

OCT 23 1985

Notary Public

My Commission expires: 5/11/87

WELL LOG

Nadel and Gussman

Stithem No. 24

SE NE NE 14-10-20W
Rooks County, Kansas

Comm: 1-8-57

Comp: 1-18-57

Casing: 8-5/8" 192' w/100 sax
5-1/2" 3236' w/150 sax

Formations

Depth

Shale and sand	192
Shale	880
Sand and shale	1400
Shale	1490
Shale and shells	1625
Anhydrite	1665
Shale	1690
Shale and shells	2100
Lime and shale	2225
Lime	2360
Shale and lime	2675
Shale	2850
Shale and lime	3310
Lime	3645
Lime and Conglomerate	3720
Shale and Arbuckle	3738

Geological Tops

Topeka Lime	3208
Heebner Shale	3412
Toronto Lime	3433
Lansing-Kansas City	3449
B. Kansas City	3662
B. Penn Cong.	3687
Simpson Shale	3723
Arbuckle Dolomite	3735

STATE OF KANSAS)
COUNTY OF SEDGWICK) **SS:**

L. C. Hay, of lawful age, states that the above formations and depths are correct to his best knowledge and belief.

L. C. Hay

Subscribed and sworn to before me this 31st day of January, 1957.

Row Buss
Notary Public

My commission expires Nov. 3, 1960

RECEIVED
STATE CORPORATION COMMISSION

8-8-
AUG 8

CONSERVATION COMMISSION
Wichita, Kansas