

STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME STITHEM

WELL NUMBER 25

SPOT LOCATION NE SE NW

SEC. 14 TWP. 10 SRGE. 20 ~~6500~~ (W)

COUNTY Rooks

Date Well Completed 1/28/57

Plugging Commenced 7/21/87

Plugging Completed 7/21/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower
Tulsa, OK 74103

PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #4 Hays, KS

Is ACO-1 filed? N/A If not, is well log attached? yes

Producing formation Lansing/K.C. Depth to top 3672 bottom 3678 T.D. 3779

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8	202	none
				5-1/2	3775	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.


Cut off 5-1/2" csg. and pumped 150 sacks ATL cement # 200# hulls down 8-5/8" & 5-1/2" casing
Maximum pressure 250#
Witnessed by KCC Rep: Dennis Hamel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No.
Address P.O. Box 31 Russell, KS 67665

STATE OF Oklahoma COUNTY OF Tulsa, ss.

M. R. Taylor (employee of operator) or (operator) of above-described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



AUG 3 1987
8-3-1987
CONSERVATION DIVISION
Wichita, Kansas

(Signature) M R Taylor
3232 First National Tower
(Address) Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 31 day of July, 19 87

Mildred Carter
Notary Public

My Commission expires: 5/11/91

WELL LOG

15-103-02102-00-00

Nadel and Gussman

Stithem No. 25

NE SE NW 14-10-20W
Rooks County, Kansas

Comm: 1-19-57
Comp: 1-28-57

Casing: 8-5/8" 202' w/125 sax
5-1/2" 3774' w/150 sax

Formations

Depth

Shale 205
Shale and shells 1664
Anhydrite 1705
Shale 2125
Shale and shells 2315
Shale and lime 2570
Shale 2800
Shale and lime 3390
Lime 3715
Lime-Conglomerate 3779

Geological Tops

Heebner 3451
Toronto 3475
Lans-Kansas City 3490
B.Kansas City 3704
Conglomerate 3733
Simpson 3754
Arbuckle 3773

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

L. C. Hay, of lawful age, states that the above formations and depths are correct to his best knowledge and belief.

L. C. Hay

Subscribed and sworn to before me this 31st day of January, 1957.

Paul B. ...

Notary Public

My commission expires Nov. 3, 1960

RECEIVED
STATE CONSERVATION COMMISSION

8-3-1987
AUG 3 1987

CONSERVATION DIVISION
Wichita, Kansas