

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Rooks SEC. 14 TWP. 10S RGE. 20W ~~E/W~~  
Location as in quarters or footage from lines:  
NW SE NE


Lease Owner Nadel and Gussman  
Lease Name STITHEM Well No. 11  
Office Address 3232 First National Tower-Tulsa, OK 74103  
Character of Well (Completed as Oil, Gas or Dry Hole): oil  
Date Well Completed Sept. 28, 1951  
Application for plugging filed 8/30/82  
Plugging commenced 9/16/82  
Plugging completed 9/16/82  
Reason for abandonment of well or producing formation Depleted

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel & Carl Goodrow  
Producing formation Arbuckle Depth to top 3748 bottom 3751 T.D. 3751  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
<u>Arbuckle</u>	<u>oil(depleted)</u>	<u>3748</u>	<u>3751</u>			
				<u>8-5/8"</u>	<u>149'</u>	<u>none</u>
				<u>5-1/2"</u>	<u>3749'</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from        feet  
to        feet for each plug set.

250 sacks of 50/50 Poz, 6% gel, 3% calcium chloride, and 3 sacks of hulls  
were pumped down the 8-5/8" and 5-1/2" annulus at the same time.  
SIP 400#.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 01 1982  
10-1-1982  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Allied Cementing Company (Russell, Ks.)

STATE OF Oklahoma COUNTY OF Tulsa, ss.  
M. R. Taylor, Mgr, of Prod. (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) M R Taylor  
3232 First National Tower-Tulsa, OK 74103  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 19 82

Mildred Carter  
Mildred Carter Notary Public.

My Commission expires: 5/11/83



WELL LOG

Nadel and Gussman

STITHEM No. 11

NW SE NE 14-10-20W  
Rooks County, Kans.

Comm: 9-20-51  
Comp: 9-28-51

Casing: 8-5/8 @ 149' w/100 S.  
5-1/2 @ 3749' w/100 S/

Formation	Depth
Surface	149
Shale and shells	815
Shale, shells, red bed & sand	1480
Sand and shale	1645
Anhydrite	1680
Shale, shells and red bed	1900
Shale and shells	2280
Broken lime	2420
Broken lime and lime	2510
Broken lime	2535
Shale and lime	3482
Lime	3680
Lime and Conglomerate	3722
Conglomerate, Simpson and Arbuckle.	3751

GEOLOGICAL TOPS

Heebner	3420
Toronto	3446
Lansing-Kansas C.	3459
Conglomerate	3704
Simpson Shale	3744
Arbuckle	3748-51 T.D.

RECEIVED  
STATE CORPORATION COMMISSION  
9-1-1982  
SFP 1 1982  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) SS:  
COUNTY OF SEDGWICK )

L. C. Hay, of lawful age, deposes and states that the above formations and depths are true and correct as shown by the daily drilling log of the Stithem No. 11 well in the NW SE NE 14-10-20W, Rooks County, Kansas.

Subscribed and sworn to before me this 2nd day of October, 1951.

L. C. Hay  
Notary Public

My commission expires Nov. 3, 1952